


# City of Vacaville Groundwater Management Plan Update



Prepared by:
Luhdorff & Scalmanini, Consulting Engineers
Woodland, California



February, 2011





#### **TABLE OF CONTENTS**

| 1.0 | INTRODUCTION   | 1  |
|-----|--|----|
| 1.  |  |    |
|     | 1.1.1 City of Vacaville  |    |
|     | 1.1.2 Authority for Groundwater Management   |    |
| 1   | ·  |    |
|     | 1.2.1 Agency Coordination  |    |
|     | 1.2.2 Integrated Regional Water Management Plan  |    |
| 1.  | 3 CITY WATER SUPPLY  | 3  |
| 1.  | 4 LEGISLATION RELATED TO GROUNDWATER MANAGEMENT PLANS  | 3  |
| 1.  | ORGANIZATION OF GROUNDWATER MANAGEMENT PLAN  | 6  |
| 2.0 | SUMMARY OF CITY WATER SUPPLIES AND GROUNDWATER   | _  |
|     | CONDITIONS   |    |
| 2.  |  |    |
|     | <ul><li>2.1.1 Sacramento Valley Basin, Solano Subbasin (Basin Number: 5-21.66)</li><li>2.1.2 Suisun-Fairfield Valley Basin (Basin Number: 2-3)</li></ul> |    |
|     | 2.1.2 SOURCES OF SUPPLY  |    |
|     | 2.2.1 City of Vacaville Pumpage  |    |
|     | 2.2.2 Other Pumpage in Northern Solano County  |    |
|     | 2.2.3 Conjunctive Water Use and Management   |    |
| 2.  | 3 GROUNDWATER CONDITIONS   | 11 |
|     | 2.3.1 Hydrogeology   | 11 |
|     | 2.3.2 Groundwater Levels   |    |
|     | 2.3.3 Comparison of Groundwater Level Responses in Different Aquifer Zones   |    |
|     | 2.3.4 Groundwater Quality  |    |
| 2.4 |  |    |
| 3.0 | GROUNDWATER MANAGEMENT PLAN OBJECTIVES AND   |    |
| 3.0 | COMPONENTS   | 19 |
| 3.  | 1 GROUNDWATER MANAGEMENT PLAN OBJECTIVES   | 19 |
| 3.  | 2 PLAN CATEGORIES AND COMPONENTS   | 20 |
| 3.  | 3 COMPONENT CATEGORY 1: MONITORING PROGRAM   | 21 |
|     | 3.3.1 Component 1A: Elements of Monitoring Program   |    |
|     | 3.3.2 Component 1B: Evaluation and Reporting of Monitoring Data  |    |
|     | 4 COMPONENT CATEGORY 2: WATER RESOURCE SUSTAINABILITY  |    |
|     | 3.4.1 Component 2A: Maintaining Stable Groundwater Levels  | 26 |

|      | 3.4.2 Comp | onent 2B: Determination of Sustainable Pumpage                           | .27 |
|------|------------|--|-----|
|      | 3.4.3 Comp | onent 2C: Continuation of Conjunctive Use Operations                     | .28 |
|      | 3.4.4 Comp | onent 2D: Water Conservation   | .29 |
| 3.5  | COMPON     | ENT CATEGORY 3: GROUNDWATER RESOURCE PROTECTION                          | .31 |
|      |            | onent 3A: Well Construction and Destruction Policies                     |     |
|      | -          | onent 3B: Identification and Management of Recharge Areas and Wellhead   |     |
|      | -          | ction Areas  | .32 |
|      |            | onent 3C: Management and Mitigation of Contaminated Groundwater          |     |
|      | -          | onent 3D: Long-Term Salinity Management Programs                         |     |
| 3.6  | COMPON     | ENT CATEGORY 4: AGENCY COORDINATION AND PUBLIC OUTREACH                  | .35 |
|      |            | onent 4A: Continuation of Local, State, and Federal Agency Relationships |     |
|      | =          | onent 4B: Public Outreach  |     |
|      | •          | onent 4C: Water Awareness Education                                      |     |
|      | •          | ENT CATEGORY 5: PLAN IMPLEMENTATION AND UPDATES                          |     |
|      |            | onent 5A: Plan Implementation and Reporting                              |     |
|      | -          | onent 5B: Provisions to Update the Groundwater Management Plan           |     |
|      | ·          | ·  |     |
| 4.0  | KEFEK      | ENCES  | 40  |
|      |            |  |     |
|      | . =0       |  |     |
| IAB  | BLES       |  |     |
|      | Table 2-1  | City of Vacaville Water Supply   |     |
|      | Table 2-2  | City of Vacaville Water Supply Summary                                   |     |
|      | Table 2-3  | City of Vacaville Water Supply Sources in Normal Year                    |     |
|      | Table 2-4  | City of Vacaville Annual Well Production                                 |     |
|      | Table 2-5  | Groundwater Quality Northern Solano County                               |     |
|      | Table 3-1  | City of Vacaville Groundwater Monitoring Program                         |     |
|      | Table 3-2  | Summary of SCWA Monitoring Well Construction                             |     |
|      | Table 3-3  | Summary of Action Items  |     |
| FIGI | JRES       |  |     |
|      |            | City of Vacaville Location Map   |     |
|      | •          | Groundwater Basins and Subbasins   |     |
|      | _          | Water Purveyors in Northern Solano County                                |     |
|      | _          | Location Map with Groundwater Monitoring Facilities                      |     |
|      | _          | City of Vacaville Annual Groundwater Pumpage                             |     |
|      | _          | Surficial Geologic Map of Solano County                                  |     |
|      |            | Cross-Section E-E'   |     |
|      | •          | Isopach Contour Map Basal Tehama Formation                               |     |
|      | _          | Groundwater Level Hydrograph City of Vacaville, Well No. 8               |     |
|      | _          | Subsidence Monitoring Vacaville Area                                     |     |
|      | _          | Well Location Map  |     |
|      | _          | Well Location Map for Hydrographs on Figure A-3                          |     |

- Figure A-3 Hydrographs of Groundwater Elevations by Zone
- Figure A-4 Representative Hydrographs of Basal Zone Wells
- Figure A-5 Hydrographs, City Well No. 15 and Nearby Monitoring Wells
- Figure A-6 Hydrographs, City Well No. 16 and Nearby Monitoring Wells
- Figure A-7 Contours of Equal Groundwater Elevation Spring 2009
- Figure A-8 Contours of Equal Groundwater Elevation Fall 2009
- Figure A-9 Contours of Equal Groundwater Elevation Spring 2010
- Figure A-10 Contours of Equal Groundwater Elevation Fall 2010

#### **APPENDICES**

Appendix A

#### 1.0 INTRODUCTION

#### 1.1 CITY DESCRIPTION AND OVERVIEW

#### 1.1.1 City of Vacaville

The City of Vacaville, founded in 1850, is located at the base of the Vaca Mountains, approximately halfway between Sacramento and San Francisco on Interstate 80 (**Figure 1-1**). The City limits encompass over 21 square miles with a population in excess of 92,000, which makes Vacaville the third largest city in Solano County.

Water demand has increased as the City's population grew from about 43,400 in 1980 to 71,500 in 1990 and 92,000 in 2009. The rate of growth has been slower in recent years, and recently imposed growth measures are expected to ensure adequate water supply for the community (Nolte, 2005).

#### 1.1.2 Authority for Groundwater Management

The City of Vacaville is a local public agency that provides water service to customers within the City limits. As a result of Assembly Bill (AB) 3030, the California Water Code (CWC), Section 10750 *et seq.*, provides local agencies with the authority to adopt and implement groundwater management plans. On March 9, 1993, the City Council of Vacaville voted to adopt a resolution of intent to draft a groundwater management plan, and following the requirements of the CWC at that time, the City passed a resolution on February 14, 1995 approving the *City of Vacaville AB* 3030 Groundwater Management Plan (West Yost, 1995). As described further below, the CWC was subsequently amended as a result of Senate Bill (SB) 1938 (Machado), effective January 2003. As a result, the City has prepared this updated Groundwater Management Plan to comply with the revised requirements.

#### 1.1.3 Plan Purpose

The purpose of the Plan is to maintain a high quality, reliable, and sustainable water supply for the citizens of Vacaville. To accomplish this, the City will continue to manage groundwater conjunctively with its surface water resources and support groundwater basin management objectives directed toward the sustainability of groundwater supplies. Groundwater management involves the ongoing performance of coordinated actions related to groundwater withdrawal, replenishment, and protection to achieve long-term sustainability of the resource without detrimental effects on other resources. To accomplish the City's purposes and the regional basin management objectives, the Plan sets forth a framework and related actions necessary to meet those objectives.

#### 1.2 OVERVIEW OF REGIONAL PLANNING EFFORTS

#### 1.2.1 Agency Coordination

The City is one of the member agencies of the Solano County Water Agency (SCWA), which encompasses all of Solano County plus the University of California at Davis (UCD) and the Yolo County portion of Reclamation District No. 2068 (RD 2068). SCWA was established in 1951 as the Solano County Flood Control and Water Conservation District (SCFC&WCD) under the governance of the Solano County Board of Supervisors. The governing board was expanded in 1988 to include the Solano County Board of Supervisors; mayors of the cities of Vallejo, Benicia, Suisun City, Dixon, Rio Vista, Fairfield, and Vacaville; Solano Irrigation District (SID); Maine Prairie Water District (MPWD); and RD 2068. The SCFC&WCD changed its name to SCWA in 1989. SCWA is responsible for water supply and flood control within its service area. Its water supply role consists of providing untreated surface water to cities, water districts, and state agencies within its boundaries. Other stakeholders that are not SCWA members include Rural North Vacaville Water District (RNVWD), the Dixon-Solano Municipal Water Service (DSMWS), and California Water Service Company (CWSC).

SCWA's primary source of water is the Solano Project, which stores water in the Lake Berryessa Reservoir created by the construction of Monticello Dam on Putah Creek in 1957. Other Solano Project facilities include the Putah Diversion Dam and the Putah South Canal, which delivers Solano Project water to the City and other recipients.

The City is also a member of the Solano Water Authority (SWA), which is a joint powers authority formed in 1987 with the same membership as SCWA. The SWA conducts its work through project agreements; one of these projects, the Coordinated Groundwater Data Analysis Project or SWA-4, is responsible for groundwater data management in northern Solano County. SWA prepares periodic reports to summarize the compiled data and describe historical and current groundwater conditions. Participants in this project include the cities of Vacaville and Dixon, SID, MPWD, RD 2068, SCWA, and Solano County.

Four local agencies, including the City of Vacaville, SID, MPWD, and RD 2068, each adopted groundwater management plans prior to the 2003 CWC amendments. In 2004 and 2005, SCWA facilitated a coordinated effort among these agencies directed toward updates of these plans such that the plans would comply with the amended CWC and also to accomplish consistency among the plans to achieve basin management objectives (West Yost, 2006).

#### 1.2.2 Integrated Regional Water Management Plan

An Integrated Regional Water Management Plan (IRWMP) was prepared in 2005 (Solano Agencies, 2005) for the Solano agencies, including SCWA and its member entities, that identifies and prioritizes all water related actions for these Solano County agencies. Among the highest priorities noted in the IRWMP are conjunctive water resources management and groundwater management. The City and other SWA-4 entities have actively participated in steps to implement the IRWMP.

#### 1.3 CITY WATER SUPPLY

The City's water utility system was purchased from the Pacific Gas and Electric Company in 1959 by issuing voter-approved water revenue bonds (Nolte, 2005). Since that time, the City has systematically improved and upgraded the water utility system. Today, the City's system consists of transmission and distribution pipelines, storage reservoirs, wells, pumping facilities, and water treatment facilities. The system receives water from several sources, including Solano Project water from the Lake Berryessa Reservoir, State Water Project (SWP) water and Settlement Water from the North Bay Aqueduct (NBA), and groundwater from local City wells. The percentage of water used from each supply source varies due to the City's conjunctive management of its water resources. Prior to completion of the Solano Project, all water supplies provided for municipal purposes were developed from local groundwater. The City has received Solano Project water through an agreement with SCWA since 1959. In 1995, the City entered into a Water Master Agreement with SID that increases the City's allocation from this source until the year 2045. The City has also received surface water allocations from the SWP and from a purchase agreement with Kern County Water Agency. Settlement Water is not considered SWP water but consists of surface water from the Sacramento River and Sacramento-San Joaquin Delta estuary diverted under water rights held by the California Department of Water Resources (DWR). This water is made available by DWR in settlement of area-of-origin water right applications by the cities of Vacaville, Fairfield, and Benicia. The City would receive an increasing supply from SID through the year 2040 followed by a consistent supply of 10,050 AF until the year 2050 (City, in process). In aggregate, the estimated water resources available to the City in the year 2030 total 42,000 acre-feet (AF), including about 8,000 AF of groundwater (19% of the total supply).

#### 1.4 LEGISLATION RELATED TO GROUNDWATER MANAGEMENT PLANS

The Legislature enacted legislation in 1992 (AB 3030) and 2002 (SB 1938), now incorporated in the CWC Section 10753, *et seq.* to encourage local public agencies to adopt plans to manage groundwater resources within their jurisdictions. The City is updating its Groundwater Management Plan to be compliant with revisions to the CWC that resulted from SB 1938.

SB 1938 provided that adoption of a groundwater management plan will be a prerequisite to obtaining funding assistance for groundwater projects from funds administered by DWR. To comply with SB 1938, a groundwater management plan must include components that address monitoring and management of water levels, groundwater quality degradation, inelastic land subsidence, and changes in surface flows and quality that either affect groundwater or are affected by groundwater pumping. SB 1938 specifies that groundwater management plans contain provisions to cooperatively work with other public (and presumably private) entities whose service areas or boundaries overlie the groundwater basin. Provisions must also be made to allow participation by interested parties in development of the plan. The plan must include mapping of the groundwater basin, as defined in DWR's Bulletin 118, along with the boundaries of the local agencies that overlie the basin. In this case, the Plan focuses on that portion of the Solano Subbasin that underlies the City. Finally, to comply with SB 1938, monitoring protocols must be designed to detect changes in groundwater levels, groundwater quality, inelastic land

subsidence (for basins where subsidence has been identified as a potential problem), and flow and quality of surface water that either directly affect groundwater, or are directly affected by groundwater pumping.

The potential components of groundwater management plans are listed in CWC Section 10753:

- the control of saline water intrusion;
- identification and management of wellhead protection areas and recharge areas;
- regulation of the migration of contaminated groundwater;
- the administration of a well abandonment and well destruction program;
- mitigation of conditions of overdraft;
- replacement of groundwater extracted by water producers;
- monitoring of groundwater levels and storage;
- facilitating conjunctive use operations;
- identification of well construction policies;
- the construction and operation by the local agency of groundwater contamination cleanup, recharge, storage, conservation, water recycling, and extraction projects;
- the development of relationships with state and federal regulatory agencies; and
- the review of land use plans and coordination with land use planning agencies to assess activities that create a reasonable risk of groundwater contamination.

In 2002, SB 1938 amended and added to CWC Section 10750 *et seq*. regarding the implementation of local groundwater management plans. While the provisions of SB 1938 did not alter the potential components of a local groundwater management plan, as listed above, it added the following provisions:

- The local agency, in preparing a groundwater management plan, shall make available to the public a written statement describing how interested parties may participate in developing the plan. For that purpose, the local agency may appoint, and consult with, a technical advisory committee consisting of interested parties.
- In order to qualify for funding assistance for groundwater projects, for funds administered by DWR, a local agency must accomplish all the following relative to groundwater management (CWC 10753.7(a)):
  - Prepare and implement a groundwater management plan that includes basin management objectives for the groundwater basin that is subject to the plan.
  - O Include groundwater management components that address monitoring and management of water levels, groundwater quality degradation, inelastic land subsidence, and changes in surface flows and quality that either affect groundwater or are affected by groundwater pumping.
  - o Include provisions to cooperatively work with other public (and presumably private) entities whose service area or boundary overlies the groundwater basin.
  - o Include mapping of the groundwater basin, as defined in DWR's Bulletin 118,

- and the boundaries of the local agency subject to the plan, plus the boundaries of other local agencies that overlie the basin.
- Adopt monitoring protocols designed to detect changes in groundwater levels, groundwater quality, inelastic land subsidence (for basins where subsidence has been identified as a potential problem), and flow and quality of surface water that either directly affect groundwater, or are directly affected by groundwater pumping.

Of the potential groundwater management activities listed in CWC Section 10753.8, those already being investigated and actively implemented as part of less formal groundwater management by the City include avoidance of overdraft, implementation of conjunctive use, monitoring of groundwater levels and quality, initiation of groundwater contamination control, analysis of basin yield for ongoing avoidance of overdraft, and regular analysis and reporting on groundwater conditions. The historic focus of informal groundwater management by the City has been on the quantity and quality of water supply, including avoidance of overdraft conditions, primarily by augmenting local groundwater supplies with supplemental, imported surface water resources. More recently, efforts have been added to include ongoing monitoring and the compilation of data into a database system. Recent efforts have also included use of an analytical groundwater model of the greater Vacaville area for analysis of aquifer system response to various groundwater extraction scenarios for a 20-year horizon. This work also provides an initial foundation for the future development of a numerical groundwater flow model that would be used to evaluate water supply, recharge, and conjunctive use alternatives that might be applicable to the basin. The City withdraws groundwater for municipal purposes from a deep aguifer, and most other extraction in the area occurs from overlying aguifers. Because there is much less risk of contamination of the deep aquifer as compared to shallow aquifers, the City's groundwater management provisions have focused more on supply and less on groundwater contamination. However, this component of local groundwater management is important in terms of overall basin management objectives as described in more detail herein.

In summary, the City has had a formal AB 3030 Groundwater Management Plan since 1995. The City is updating its current plan to be compliant with the SB 1938 requirements as part of its interest in developing and sustaining reliable water supplies to meet its own and also basin needs. To ensure the reliability of groundwater supplies to meet existing and projected demands, the components of local groundwater management planning already implemented include a monitoring program, formulation and maintenance of a database to manage the monitoring data, analysis of and annual reporting on groundwater conditions in the basin, initiation of groundwater modeling, ongoing conjunctive use of local groundwater and imported surface water supplies, and coordination with other agencies on the control of localized groundwater contamination.

#### 1.5 ORGANIZATION OF GROUNDWATER MANAGEMENT PLAN

The balance of this plan is organized to describe management objectives, or goals, for the basin; describe existing groundwater basin conditions, including areas of concern and identified problems; present historical and projected water demands by the City from the basin; and finally to present a set of groundwater management actions which, collectively, form the components of this Groundwater Management Plan.

## 2.0 SUMMARY OF CITY WATER SUPPLIES AND GROUNDWATER CONDITIONS

#### 2.1 GROUNDWATER BASIN DESCRIPTIONS

As shown on **Figure 2-1**, the City of Vacaville overlies portions of two DWR-designated groundwater basins. The City primarily overlies the northwestern portion of the Solano Subbasin, which is one of 18 subbasins in the Sacramento Valley Basin of the Sacramento River Hydrologic Region. A small area in the southern portion of the City overlies the Suisun-Fairfield Valley Basin in the San Francisco Bay Hydrologic Region. The western portion of the City, west of the Solano Subbasin boundary, is located in the Sacramento River Hydrologic Study Area but does not overlie any area currently designated by DWR as a groundwater basin or subbasin (**Figure 2-1**).

All of the City's existing and proposed municipal wells are located in the Solano Subbasin. **Figure 2-2** also shows the other major purveyors in the northern portion of the subbasin. These include the City of Dixon, SID, RNVWD, MPWD, and RD 2068. Descriptions of the Solano Subbasin and the Suisun-Fairfield Valley Basin are provided below. These descriptions are partly based on the information contained in *California's Groundwater*, *Bulletin 118 Update* 2003 (DWR, 2003). For the Solano Subbasin, a more detailed groundwater basin description is posted on the DWR web site (DWR, 2010).

#### 2.1.1 Sacramento Valley Basin, Solano Subbasin (Basin Number: 5-21.66)

The Solano Subbasin includes the southernmost portion of the Sacramento Valley Basin and extends into the northern portion of the Sacramento-San Joaquin Delta. Overall, population density within the subbasin is sparse, with the major cities being Vacaville, Dixon, and Rio Vista. Subbasin boundaries are defined by Putah Creek on the north, the Sacramento River on the east (from Sacramento to Walnut Grove), the North Mokelumne River on the southeast (from Walnut Grove to the San Joaquin River), and the San Joaquin River on the south (from the North Mokelumne River to the Sacramento River). The western subbasin boundary, which extends through a portion of the City, is partly defined by the groundwater divide between the San Francisco Bay and Sacramento River Hydrologic Regions as described by DWR (2010). DWR reports that the location of the divide is roughly delineated by the English Hills (a section of the Coast Range south of Putah Creek and north of Vacaville) and the Montezuma Hills. There is an area west of the Solano Subbasin between the subbasin boundary and the Lagoon Valley/Vaca Valley fault in which some groundwater development has occurred, but which does not lie within a designated basin or subbasin area.

#### 2.1.2 Suisun-Fairfield Valley Basin (Basin Number: 2-3)

The Suisun-Fairfield Valley Basin is composed of low alluvial plains, with surrounding foothills and mountains, located immediately north of Suisun Bay. The foothills of the Coast Ranges, lying west of Green Valley, bound the basin on the west. The southern extent of the Vaca Mountains forms the northern boundary of the basin. The eastern extent of the basin is marked by low ridges of consolidated rock that appear near the City and extend southeast to the Montezuma Hills (Thomasson et al, 1960).

#### 2.2 SOURCES OF SUPPLY

As summarized in the City's General Plan Update (City, in process), the City's water supply includes both surface water and groundwater sources. The City's surface water sources are Lake Berryessa (Solano Project water) and the State Water Project (SWP) water delivered via the NBA. The balance of the City's water supply is groundwater. Current City water supplies are summarized in **Table 2-1** for normal, single-dry, and multiple-dry years. As indicated on the table, some of the Solano Project and SWP water supply is based on the City's entitlement and some is based on other agreements and settlements. The City's surface water entitlements for 2010 total 26,548 AF, but SWP deliveries are less than the entitlement in all but the wettest years. The availability of SWP water is approximately 64% of the entitlement in a normal year and is projected to decrease to 31% in a single-dry year and to 46% in a multiple-dry year. Therefore, approximately 16,991 AF of surface water would typically be available in a normal year. Total groundwater pumping by the City has decreased from 6,600 AF in 2007 to 5,068 AF in 2010. This represents a 5% reduction in the percentage of the City's total available water supplied by groundwater pumping in a normal year. Surface water use by the City of Vacaville from 2008 to October 2010 is outlined in **Table 2-2**.

Raw surface water deliveries to the City of Vacaville are regularly tested (at least quarterly) for microbiological constituents, regulated organic chemicals, inorganic chemicals, radioactivity, secondary aesthetic standards, and a series of unregulated constituents (pH, alkalinity, hardness, sodium, calcium, potassium, manganese, asbestos, bromide and total organic carbon). The surface water deliveries received by the City are typically high quality with the majority of constituents consistently falling below detection limits.

Projected water supply sources in future years are summarized in **Table 2-3**. Surface water supplies are expected to increase from 16,991 AF in 2010 to 21,754 AF in 2050. Total City groundwater pumpage in normal years is projected to increase to 8,000 AF in 2020 and 2025 as new City wells come on line.

#### 2.2.1 City of Vacaville Pumpage

Prior to 1997, all City pumpage was from the Elmira Road well field, primarily from wells completed in the basal zone of the Tehama Formation but also including a small amount of pumpage from Well 1 completed in the Markley Formation. Concentrated pumpage in the Elmira Road area caused a localized cone of depression and declining groundwater levels in the basal zone. In order to alleviate this condition, the City began constructing new wells outside of the

Elmira Road area in the mid-1990s. Beginning with the construction of Well 14, which came on line in 1997, some pumpage has been redistributed from Elmira Road to the northeastern portion of the City. Two other northeast sector wells have since been constructed in the basal zone. Well 15 came on line in 2004, and Well 16 came on line in 2007. Construction of a new production well in the northeast sector, Well 17, is expected to begin in 2011. The northeast sector wells produced about 1,900 AF (41% of the total) in 2009 and 2010. The locations of existing City wells are shown on **Figure 2-3**.

The majority of the City's historical and current pumpage is from the basal zone of the Tehama Formation; Well 1 is the only non-basal zone well currently in operation. Total annual pumpage for the City from 1968 to October 2010 is shown on **Table 2-4** and **Figure 2-4**. Annual pumpage from the City's wells is divided into four categories on **Figure 2-4**:

- 1) Basal zone pumpage from the Elmira Road well field (Wells 2 through 13);
- 2) Non-basal zone pumpage from Well 1 at Elmira Road (currently less than 100 AF per year);
- 3) Basal zone pumpage from northeast sector wells (currently Wells 14, 15, and 16);
- 4) Non-basal zone pumpage from the DeMello well in the northeast sector (maximum of 160 AF per year in 2003, offline as of 2005).

The City's annual groundwater pumpage was relatively constant from 1968 to 1974, ranging from 2,862 to 3,316 AF per year. All pumpage during this period was from Elmira Road wells but was not differentiated by zone. Pumpage began to increase in 1975 and reached a peak of 8,024 AF in 1983. Pumpage decreased to 6,089 AF in 1984 and ranged from 5,421 to 6,236 AF, with an average of about 5,800 AF, during 1984 to 1992. Pumpage decreased to 4,395 AF in 1993 and continued to decrease to a low of 3,230 AF in 1996. Pumpage increased from1996 to 2002, reaching 6,638 AF in 2002. From 2002 to 2007 pumping remained relatively constant, averaging 6,635 AF per year. Since 2007, the City of Vacaville has gradually reduced the amount of groundwater it produces to 5,068 AF in 2010, which represents 31% of total use for that year. In 2007, 34% of water demand was supplied by groundwater.

Changes in the City's historical pumpage are correspondingly reflected in the water level data from the Elmira Road well field; specifically, water levels increased as pumpage decreased and vice versa. Notably, the relationship between pumpage and water level response and the development of the localized cone of depression was recognized in the 1980s (Mann, 1985). The City has since developed new groundwater supplies for municipal purposes north of Elmira Road and decreased its total pumping to reduce the local pumping depression in the Elmira Road area. Beginning with the construction of City Well 14, which came on line in 1997, roughly 40% of pumpage has been redistributed from Elmira Road to the northeast sector of the City.

Well 15, located northeast of Well 14, came on line in September 2004. Well 16, located northwest of Wells 14 and 15, was drilled in January 2005 and came on line in July 2007. The DeMello well (completed in the upper Tehama Formation) came on line in 2003, but the capacity of this well is much smaller than the basal zone wells and it has been used only for backup supply since 2004. It has been offline as of 2005. With the addition of the northeast sector wells, Elmira Road pumpage decreased from 5,549 AF in 2003 to 2,698 AF in 2009. Increased

pumpage from the northeast sector wells in future years will further decrease reliance on the Elmira Road wells.

#### 2.2.2 Other Pumpage in Northern Solano County

A brief summary of groundwater development in Solano County is contained in the IRWMP prepared in 2005. Prior to construction of the Solano Project, both municipal and agricultural users relied primarily on groundwater. Wells were perforated primarily in the Quaternary alluvium and the upper and middle zones of the Tehama Formation, and groundwater levels declined significantly in those zones. After completion of the Solano Project in 1958, most agricultural users switched to surface water, and groundwater levels recovered. Most growers in SID rely primarily on surface water, and growers in MPWD and RD 2068 use surface water exclusively (Solano Agencies, 2005).

After the City of Vacaville, SID, and the City of Dixon are the largest producers of groundwater in northern Solano County. SID operates wells to supplement surface water supplies and also to provide for drainage due to a high water table in certain areas. Although pumpage by privately owned wells in SID is unknown, annual metered pumpage is available for SID-owned wells since 1964. SID's pumpage ranged from a low of 2,311 AF during a wet year (1983) to a high of 13,965 AF during the 1976 drought year. SID's pumpage in 2005 (5,440 AF) was only slightly above the 40-year average of 5,363 AF.

The City of Dixon relies entirely on groundwater for its water supply. The City of Dixon is supplied with domestic water by California Water Service Company (Cal Water) and the Dixon-Solano Municipal Water Service (DSMWS). The City's water demand in 2005 was approximately 2,858 AF/year and is projected to be 3,899 AF/year in 2010 (Dixon, 2008).

The RNVWD also produces groundwater from the basal zone of the Tehama Formation. RNVWD pumpage was about 40 AF in 2003 (LSCE, 2003b). Pumpage by industrial and domestic wells in unincorporated portions of the Vacaville area is unmetered, but is assumed to be small. Groundwater development in the Vacaville area by others than the City has largely been from the upper part of the aquifer system rather than the basal zone of the Tehama Formation.

#### 2.2.3 Conjunctive Water Use and Management

The City conjunctively manages its groundwater and surface water resources to most effectively use those resources during different water year types. This has been previously demonstrated to be an effective and flexible management approach. Continued conjunctive water management is expected to enable the City to meet its future water demands for a 20-year horizon and beyond. Groundwater-related objectives of the conjunctive water management plan are to:

- 1) Recognize and implement actions to prevent persistent water level declines, and
- 2) Continue to maintain water levels above historical lows when levels temporarily decline during dry years to minimize adverse consequences that would result from over pumping of the aquifer system.

As discussed below, groundwater monitoring data collected by the City indicate the response of the aquifer system to variations in the City's annual pumping amounts. Spring groundwater levels measured during 1992-1993 were initially used to establish "base year" groundwater levels, or the levels to which the aquifer had recovered in response to an estimated sustainable level of pumpage. The 1992-1993 base year groundwater levels have been augmented with more complete data collected during 2002-2010. This base year groundwater level concept serves to guide conjunctive management of the City's water resources. The base year concept is used to define the "normal condition" referenced in the Master Water Agreement between the City of Vacaville and SID signed on May 25, 1995. This plan was developed to ensure sustainable groundwater supplies in the City and SID service areas.

Base year water levels are not anticipated to be exceeded during "normal" water years (i.e., precipitation amount referred to as normal) in response to the pumpage associated with those years. The concept also recognizes that if pumpage is increased during single-dry or multiple-dry years, water levels would temporarily decline to below base year levels in response to increased pumpage. Following a short-term water level decline during a dry year with increased pumping, the base year groundwater levels provide a target to which to restore water levels.

#### 2.3 GROUNDWATER CONDITIONS

#### 2.3.1 Hydrogeology

Most City and non-City wells in the Vacaville area are completed in the Tehama Formation, which has been subdivided into upper, middle, and basal zones. The City's wells are largely completed in the basal zone of the Tehama Formation. City Well 1 is also partially completed in older pre-Tehama deposits. Shallow wells are typically completed in the upper zone of the Tehama Formation and the overlying Quaternary alluvium. A geologic map is provided as **Figure 2-5** to illustrate the regional geology. A detailed discussion of the regional geologic setting, including geologic cross sections, is provided in *Hydrostratigraphic Interpretation and Groundwater Conditions of the Northern Solano County Deep Aquifer System* (LSCE, 2010). A brief summary of geologic conditions is provided below.

The Pliocene and Pleistocene Tehama Formation is the primary aquifer for agricultural and municipal water supply in northern Solano County, including the Vacaville area. This formation consists of slightly to moderately consolidated fluvial, alluvial, and lacustrine deposits and includes interlayered clay, silt, sand, and gravel beds. A stiff blue lacustrine clay found near the upper boundary of the formation and other relatively continuous clay layers divide the formation into upper, middle, and basal zones.

In the Vacaville area, the continuous clay layers within the Tehama Formation appear to thin to the west-southwest, with some layers pinching out altogether. The Tehama Formation has a thickness of up to 2,200 feet in the vicinity of the City's eastern boundary and an outcrop area of over 35 square miles in the English Hills, north of the City, and continuing north toward the Solano County line (**Figure 2-5**). This outcrop serves as the primary recharge area for the Tehama Formation.

The upper and middle zones of the Tehama Formation are used for domestic and agricultural water supply. Southwest of the Highway 80/Midway Road junction, these zones are characterized by predominately thick, fine-grained silt and clay with a few thin sand and gravel beds. Northeast of this area, the number of coarser-grained beds appears to increase. In most western areas, the fine-grained nature, discontinuity of the sands, and generally low yields make these zones unsuitable for high capacity municipal water wells. Typically, these zones are only capable of producing 100 to 300 gallons per minute (gpm) with specific capacities of less than 2 gallons per minute per foot (gpm/ft), although some wells can produce up to 1,000 gpm. Aquifer test data in the upper zone are limited, but a transmissivity of only 1,500 gallons per day per foot (gpd/ft) was estimated based on a test of the City's DeMello well. Reliable transmissivity estimates are not available for the middle zone.

The basal zone of the Tehama Formation includes gravel and cobble deposits and layers of volcanic tuff and conglomerate cemented with calcium carbonate. The more permeable portions of the basal zone are comprised primarily of gravelly sand with calcium carbonate cementation in some areas. The basal zone occurs near the surface on the western edge of the City's Elmira Road well field and gradually deepens to the east (Figure 2-6, basal zone outlined in blue). The basal zone ranges in thickness from less than 400 feet in the Elmira Road area, to greater than 700 feet between Vacaville and Dixon (**Figure 2-7**). Up to 350 feet of this zone yields significant quantities of groundwater. The bottom of the basal zone occurs at a depth of about 2,400 feet in the vicinity of the City's Easterly Wastewater Treatment Plant and near the Midway Road/Highway 80 junction area. East of these areas, the basal zone appears to contain finegrained sand beds. Detailed correlations using numerous oil and gas test holes with geophysical logs indicate that the basal zone extends beneath the Dixon area at a depth of 2,000-2,500 feet. The top of the basal zone was encountered at 1,980 feet bgs during construction of a multiple completion monitoring well in the Dixon area for SCWA (LSCE, 2010). Regional correlations suggest a finer-grained sandy zone extending eastward to beneath the Davis area at depths below existing municipal wells. However, the yield and water quality of this zone are presently unknown.

Specific capacities of wells completed in the basal zone in the Vacaville area generally range from 4 to 24 gpm/ft, depending on the thickness of aquifer materials encountered by the well and included in the perforated interval. The City's municipal basal zone wells range in capacity from 500 to 1,800 gpm. The mean transmissivity of the basal zone is roughly 48,000 gpd/ft (LSCE, 2003a; LSCE, 2008). The transmissivity is significantly lower to the north in the RNVWD wells (mean of about 17,000 gpd/ft).

The Lagoon Valley/Vaca Valley fault flanks the eastern side of the Vaca Mountains and was recognized by Thomasson (1960) and others. The Lagoon Valley/Vaca Valley fault is an extension of the Vaca-Kirby Hills fault and is interpreted as a high-angle, northwest striking, east dipping, normal fault associated with Miocene to Pliocene age uplift and volcanism. Data to determine the hydraulic properties of this fault are limited, and it is unknown whether the fault affects groundwater flow.

#### 2.3.2 Groundwater Levels

Groundwater level data for the City's wells are available from the City's monitoring program, which is discussed in Section 3.3. The monitoring program includes semi-annual manual water level measurements in 13 production wells and 11 monitoring wells. In addition to the manual measurements, nine production wells are also monitored electronically with transducers connected to the City's Supervisory Control and Data Acquisition (SCADA) system. Groundwater levels in other wells in and near the City are also monitored at least semi-annually by (or on behalf of) other entities, including SCWA, DWR, the U.S. Bureau of Reclamation (USBR), SID, and RNVWD (Figure A-1).

Representative water level hydrographs for the Vacaville area are provided in **Appendix A** (**Figures A-3 and A-4**). The hydrographs included in **Appendix A** are organized according to the four primary formations in which the wells are completed: Quaternary alluvium and the upper, middle, and basal zones of the Tehama Formation (**Figure A-2**). Groundwater elevation contour maps prepared for the basal zone of the Tehama Formation are also included in **Appendix A** (**Figures A-7 to A-10**) to indicate the hydraulic gradient and direction of groundwater flow beneath the City.

Water levels in wells completed in Quaternary alluvium and the upper zone of the Tehama Formation (**Figure A-3**) show similar trends. Water levels in those zones generally show declining levels from the 1940s to the early 1960s as a result of increasing groundwater pumpage. Beginning in the 1960s, water levels rose following the delivery of surface water from the Solano Project and corresponding reductions in groundwater pumpage. Water levels have remained relatively high since the late 1960s, largely unaffected by wet or dry climatic periods, with depths to water typically less than 10 feet. Groundwater levels in the Quaternary alluvium and upper zone of the Tehama Formation show small seasonal effects with slightly higher groundwater levels in the spring. Water levels in these relatively shallow aquifers appear to be unaffected by basal zone pumpage.

Water level data are more limited for wells completed in the middle zone of the Tehama Formation. **Figure A-3** illustrates groundwater levels for two wells (6N/1W-23C1 and 7N/1W-34F1) monitored by DWR in the Vacaville area that had sufficient historical data to indicate water level trends in this zone. Groundwater level trends in these wells are generally similar to those observed in the upper zone of the Tehama Formation. Also shown in **Figure A-3** are two monitoring wells (Rural North Vacaville Water District (RNVWD) MW-446 screened between 426 and 436 feet and RNVWD MW-594 screened between depths of 564 to 584 feet) located near RNVWD production Well No. 1. Groundwater levels in the RNVWD monitoring wells show declining groundwater levels until about 2008. The trends in these wells are likely due to local pumping effects from the RNVWD water supply well and a higher level of hydraulic connectivity between the middle and deeper (basal) Tehama Formation deposits.

Water level data since 2000 for the basal zone of the Tehama Formation are shown in (**Figure A-4**). A response to reduced pumping since 2008 can be seen in all of the wells shown. A detailed hydrograph of City Well 8 at Elmira Road shows a typical water level response to pumpage for the City's basal zone wells since 1988 (**Figure 2-8**). In order to obtain generally static

measurements, manual water level measurements in the City's wells since 1992 have been preceded by a three-day shutdown period that eliminated the most pronounced effects of recent pumping by one or more nearby wells to ensure consistent and generally static monitoring conditions. Beginning in 2002, selected transducer measurements from the City's SCADA system have been available to indicate the highest water levels in the spring and the lowest water levels during the summer.

As noted above, the City has considered 1992 to 1993 to represent a "base year" groundwater level condition. The maximum spring water levels in 2003 were approximately the same as 1992 for a similar level of Elmira Road pumpage (about 5,400 AF per year), and the spring 1993 and 2003 water levels are highlighted on Figure 2-8. Water level data from Well 8 reflect changes in the City's basal zone pumpage from the Elmira Road well field; specifically, water levels increase as pumpage decreases and vice versa. Elmira Road basal zone pumpage decreased from 1992 to 1996, was relatively constant from 1996 to 1999, and increased from 1999 to 2002. The City kept its total production at a constant level (between 6,600 and 6,700 AF) from 2002 through 2007, then pumpage decreased to about 5,800 AF in 2008 and to 4,600 AF in 2009. The changes in pumpage resulted in increasing water levels in Well 8 from 1992 to 1998, relatively constant water levels from 1998 to 2000, and water level declines of about 35 to 40 feet from spring 2000 to spring 2002 as pumpage increased. Spring water levels declined slightly from 2003 to 2005, recovered in 2006, and declined slightly in 2007. Hydrographs of other Elmira Road wells show water level declines from 2000 to 2005 and relatively stable water levels beginning in 2005. In spring 2009, groundwater levels in the basal Tehama Formation recovered by about 14 feet to an elevation of about -66 feet. In spring 2010, groundwater levels rose to an elevation of about -61 feet in response to further decreases in pumpage in 2009.

The City has reduced its Elmira Road basal zone pumpage by shifting more pumpage to new wells constructed in the northeast sector (Wells 14, 15, and 16). As of 2010, 42% of groundwater production occurred in the northeast sector wells, up from 30% in 2007 and 16% in 2000. Overall, this has resulted in water level declines in the northeast sector wells and reduced drawdown in the Elmira Road well field. A hydrograph of Well 14, which has the longest period of record of the northeast sector production wells, is included in **Appendix A** (**Figure A-4**). Water levels in Well 14 declined at a faster rate between 1998 and 2005 than in the Elmira Road wells (about 50 feet in seven years), stabilized between 2005 and 2007, and as discussed above, have risen since 2007.

Groundwater elevations in the basal zone are much lower than in the middle and upper zones in the Vacaville area, ranging from about 20 feet above sea level in RNVWD to 60 feet below sea level in the vicinity of the City's main well field on Elmira Road. A pumping depression in the basal zone exists in the Elmira Road area, and the gradient for groundwater flow is southerly toward this depression. North of the City, the gradient has a magnitude of approximately 45 feet per mile (measured between RNVWD MW-1389 and Vacaville MW-16 1430 2009 to 2010), which is much steeper than the gradient in the upper zone of the Tehama Formation. The gradient becomes less steep in the Elmira Road area, e.g., the gradient between Well 14 and the Elmira Road wells is only about 3 feet per mile. This is due to the northerly expansion of the cone of depression in the Elmira Road area as more pumpage has been shifted to Wells 14 and 15 in the northeast sector.

#### 2.3.3 Comparison of Groundwater Level Responses in Different Aquifer Zones

Groundwater elevations in the deeper, more confined zones of the Tehama Formation have shown considerable variation over time in direct response to changes in the amount of groundwater used as a source of supply by the City. Groundwater levels in shallower, unconfined to semi-confined aquifers (e.g., the Quaternary alluvium and the upper zone of the Tehama), in which private water supply wells are typically constructed, appear to be largely unaffected by basal zone pumpage. Groundwater levels in the shallower compared to deeper portions of the aquifer system are shown in Figures A-5 and A-6. Figure A-5 shows three monitoring wells near City Well No. 15. The shallowest well (MW-188, screened from a depth of 158 to 178 feet) shows stable groundwater elevations. Monitoring well MW-508, screened from a depth of 438 to 498 feet, also shows stable groundwater elevations. As seen in Figure A-5, water level trends in MW-188 and MW-508 are unaffected by the City's pumping. MW-1815, screened at multiple depths between 1,207 to 1,785 feet in the basal Tehama Formation, shows water level trends in response to the City's pumping. Similarly, Figure A-6 shows three monitoring wells located near City Well No. 16. As seen in **Figure A-6**, groundwater levels in the shallowest monitoring well (MW- 117 screened from 97 to 107 feet) are unaffected by the City's pumping, whereas groundwater levels measured in the two deeper monitoring wells (MW-1176 and MW-1430, which are completed in zones that are also among the zones screened by Well No. 16), show a direct response to the City's pumping.

During 1968 to 2009, the City's total groundwater production ranged from 2,862 to 8,165 AF with significant variability in pumpage during that period. Even so, groundwater levels representing the shallower part of the Tehama Formation have shown little to no effect in relation to the City's basal zone pumpage. The basal Tehama Formation is highly confined meaning there are large sections of lower permeability materials, silts and clays, which occur between the zones from which the City's wells produce groundwater and the overlying units. This confinement has caused rapid, notable responses to groundwater levels in the pumped basal zone and at the same time precludes noticeable groundwater level responses in the overlying shallower part of the aquifer system.

As the City expands groundwater development of the basal Tehama Formation in the northern to northeastern areas, similar groundwater level observations are anticipated. Specifically, it is anticipated that additional drawdown will occur in the basal zone in response to such pumping, while little or no groundwater drawdown is anticipated in the shallower part of the aquifer system. Ongoing monitoring is recommended to further evaluate groundwater level trends in relation to the City's utilization of groundwater produced from the basal Tehama Formation.

#### 2.3.4 Groundwater Quality

Historical groundwater quality data for the City's water supply wells are available from 1986 to the present, and the results are summarized in **Table 2-5**. Every three years, the City performs water quality monitoring as required for all public water supply systems. The City also collects samples annually for nitrate analysis. Water quality is generally good at all City wells, and most of the historical data do not show signs of water quality degradation. Concentrations have remained steady.

Total dissolved solids (TDS) concentrations in the basal zone wells ranged from 270 to 546 milligrams per liter (mg/L) in 2008. The TDS concentration in Well 1 was 546 mg/L in 2008, which slightly exceeds the recommended secondary Maximum Contaminant Level (MCL) of 500 mg/L but not the upper secondary limit of 1,000 mg/L. Nitrate concentrations exhibit more variability from well to well than TDS, but concentrations have been stable at most wells. Nitrate (as NO<sub>3</sub>) ranged from non-detect (<2 mg/L) in Well 16 to 19.9 mg/L in Well 5 during 2007 to 2008. Nitrate concentrations in Wells 1, 2, 5, and 13 have historically been over 10 mg/L nitrate (as NO<sub>3</sub>), but not near the MCL of 45 mg/L.

Concentrations of trace elements in the City wells have generally been low. Copper and selenium have been non-detect at all City wells; and iron, manganese, and zinc have been non-detect at most City wells. Arsenic, boron, chromium-VI, and total chromium are typically detected at relatively low concentrations (less than half the MCL), except in Well 16 where arsenic approaches, and on one occasion has exceeded, the MCL of  $10 \mu g/L^1$ .

There have been localized instances of impacts to shallow groundwater quality due to hazardous chemical contamination, but existing or potential municipal supplies have not been affected. Analyses for volatile organic compounds (VOCs) and other manmade constituents in the City's water supply wells have all been non-detect.

#### 2.3.5 Land Subsidence

Limited monitoring of land subsidence has been conducted in Solano County using leveling surveys that relied on conventional spirit level surveying equipment prior to 1985. Since 1985, conventional survey methods have largely been replaced by Global Positioning System (GPS) techniques. The results of historical spirit level and more recent GPS surveys have been combined to estimate total subsidence and subsidence rates in the southern portion of the Sacramento Valley. The greatest subsidence in the Valley, more than 20 feet in some areas, has occurred in the Delta region as a result of draining of peat soils (Blodgett et al., 1990). Subsidence north of the Delta is caused primarily by groundwater pumping, but oil and gas extraction may be responsible for a significant fraction of the total subsidence in some areas.

The only available estimate of historical land subsidence near the City is based on Ikehara's 1994 report *Global positioning system surveying to monitor land subsidence in the Sacramento Valley, California, USA* that contains estimated subsidence rates for 18 benchmarks in the southern Sacramento Valley. One of these benchmarks (X128 R71) is located approximately halfway between the cities of Vacaville and Dixon. There was approximately 2.4 feet of total subsidence at this location between 1971 and 1989, which represents a subsidence rate of 0.131 feet/year. The location of this site, along with other subsidence monitoring stations in northern Solano County and adjoining portions of Yolo County, is shown on **Figure 2-9**.

Although greater subsidence rates have occurred to the north in Yolo County, the Vacaville area is considered to have a relatively high potential for future subsidence based on the historical data, geologic conditions, and lowered groundwater levels in the basal zone, particularly in areas

16

<sup>&</sup>lt;sup>1</sup> An investigation of the elevated arsenic concentration on February 8, 2007 led to controlled operation of Well 16 to ensure the delivered water quality is within the drinking water standard for arsenic of 10  $\mu$ g/L (LSCE, 2009).

where limited development of the basal zone has occurred historically. In January 2011 two permanent GPS subsidence stations will be added to the regional monitoring network. These stations, located at City Well 16 and SCWA's Dixon monitoring well (**Figure 2-3**) will help decision makers to identify and mitigate any subsidence that may be occurring.

#### 2.4 AREAS OF CONCERN

Although groundwater conditions in the Vacaville area are generally good, there are several areas of concern that may require changes in future groundwater management. These include:

- Sustainable pumpage from the basal zone of the Tehama Formation,
- Preservation of groundwater quality, and
- Prevention of significant future land subsidence.

From 2002 to 2007 the City's total annual pumping rate was held relatively constant at 6,600 to 6,700 AF. Water level data and groundwater modeling results from that period, summarized above and in LSCE (2003a), indicate that future City pumpage from the basal zone ranging from 7,000 AF, based on existing City wells, to 8,000 AF, with additional northeast sector wells, could be sustained to meet normal-year demands. As discussed above, spring groundwater levels measured in City wells during 1992 to 1993 were used to establish "base year" groundwater levels, or the levels to which the aquifer has recovered in response to an estimated sustainable level of pumpage from the Elmira Road well field. The actual amount of sustainable basal zone City pumpage will depend on factors such as other pumping in the area, the locations and perforated intervals of future wells, and effects of climatic conditions and land use factors on groundwater recharge reaching the basal zone. More recently, it has been observed that reducing overall pumping to 4,600 to 4,700 AF has produced significant rebound in groundwater levels. It is assumed that the continued shifting of pumpage away from the Elmira Road area will enable the City to increase pumpage from the basal zone without causing future chronic water level declines. It is also expected that if the City continues to pump at the currently reduced rates, groundwater levels in and around the City of Vacaville will continue to rebound.

In general, the City's groundwater supply is of high quality and meets drinking water standards. Groundwater produced from the basal zone of the Tehama Formation contains slightly elevated arsenic concentrations at Well 16. Vertical flow within the well structure causes some water quality variability when the well is idle; as a result, the City operates this well in a manner to ensure that the produced water meets the MCL for arsenic of 10 ug/L. There have also been localized instances of impacts on shallow groundwater quality due to hazardous chemical contamination, but existing or potential municipal supplies have not been affected to date. This Plan includes recommendations for prevention, monitoring, and mitigation of future threats to groundwater quality.

Land subsidence monitoring data are very limited in the Vacaville area, but data from one USGS report discussed above show that about 2.4 feet of total subsidence occurred between Vacaville and Dixon between 1971 and 1989. There are no data to indicate how much subsidence occurred within the City limits, and especially in the vicinity of the Elmira Road well field, but historical water level declines and geologic conditions result in a potential for future subsidence. Ensuring

that groundwater levels in the basal zone do not decline below 1992 levels at Elmira Road will reduce the risk of significant future subsidence in this area. Declining water levels in the northeast sector, which have resulted from the City's more distributed pumping scheme, may increase the risk of subsidence in that area. Two subsidence monitoring stations to be added to the regional monitoring network in January 2011 will help the City to analyze any trends and mitigate impacts as needed.

## 3.0 GROUNDWATER MANAGEMENT PLAN OBJECTIVES AND COMPONENTS

#### 3.1 GROUNDWATER MANAGEMENT PLAN OBJECTIVES

The overall purpose of the Plan is to maintain a high quality, reliable, and sustainable water supply for the citizens of Vacaville. To accomplish this, the City will continue to manage groundwater conjunctively with its surface water resources and support basin management objectives (BMOs) directed toward the sustainability of groundwater supplies within the basin and subbasin. Groundwater management involves the ongoing performance of coordinated actions related to groundwater withdrawal, replenishment, and protection to achieve long-term sustainability of the resource without detrimental effects on other resources. To accomplish the City's purposes and the regional BMOs, the Plan sets forth a framework and related actions necessary to meet those objectives.

The City's utilization of surface water supplies from various sources along with local groundwater development represents a long history of water resource and water supply management actions that are consistent with what can be considered to be overall objectives for the Solano Subbasin. The BMOs addressed by this Plan can be expressed as follows:

- 1. Assessment of Groundwater Basin Conditions. Programs to monitor and report on groundwater levels, groundwater quality, and pumpage have been implemented to assess groundwater conditions in the Solano Subbasin. Plans to expand the existing programs and add monitoring of land subsidence are in progress. These monitoring programs are necessary to ensure that undesirable effects such as long-term groundwater level declines, groundwater quality degradation, and significant inelastic land subsidence are avoided. Regional coordination of groundwater monitoring is important, and monitoring programs should be reevaluated periodically to determine whether the location, depth, and frequency of monitoring is adequate. Data collected by the monitoring programs need to be evaluated on a regular basis to ensure that other BMOs are met.
- 2. **Avoidance of Progressive Groundwater Level Declines.** It is important that groundwater pumpage in the Solano Subbasin not exceed the sustainable yield of the subbasin in order to avoid chronic water level declines that could lead to overdraft conditions or cause significant inelastic land subsidence. This objective can be met through periodic evaluation of groundwater level and pumpage data collected by the monitoring program, along with refining the estimated sustainable yield of the subbasin.
- 3. **Preservation of Groundwater Quality.** This objective involves actions needed to sustain a supply of good quality groundwater for beneficial uses in the basin. It includes coordinated efforts that will be required to conduct a regional monitoring program that

identifies short and longer-term water quality trends. It also includes wellhead and recharge area protection and actions to avoid salt accumulation and/or mobility of naturally occurring constituents. Also included in this BMO will be the active characterization and solution of any groundwater contamination problems through cooperation with responsible parties or through independent action if timely response by responsible parties is not forthcoming and the preceding management objectives are thereby impacted or constrained.

4. Increased Conjunctive Use of Surface Water and Groundwater Resources. Several entities in the Solano Subbasin, including the City and SID, have used surface water and groundwater conjunctively for decades. There are opportunities to expand these programs in the future and to increase the use of recycled water to meet existing and projected demands. Included in this management objective is the non-degradation of surface water flows or quality as a result of groundwater management practices. In addition to being classified as a separate BMO, conjunctive use is one of the primary means of accomplishing BMOs 2 and 3 above.

Quantitatively, the preceding objectives translate into general preservation of groundwater levels and quality in the basin. Groundwater levels are allowed to fluctuate through seasonal demands and local hydrologic variations (wet and dry periods), but a progressive lowering of groundwater levels that could lead to overdraft would be prevented. As discussed in more detail in Chapter 2.0, the hydrogeologic setting in the Vacaville area and the City's extraction of groundwater from the deeper part of the aquifer system has resulted in large groundwater level fluctuations in the basal unit of the Tehama Formation. Fluctuations have been much smaller in the upper part of the aquifer where changes are primarily due to seasonal variations. Due to the integrated or conjunctive use of local groundwater and imported surface water, the City has managed its extraction, including locations and quantity, to prevent progressive lowering of groundwater levels in the deeper aquifer in the area beneath the City. A continuation of such local conjunctive use operations will help to accomplish the second BMO (avoidance of progressive groundwater level declines) while continuing to utilize local groundwater to meet a portion of the City's projected water requirements.

The City plans to intermittently use more groundwater from the basal zone of the Tehama Formation for dry-period and/or emergency water supply. Interpretation of historical pumping fluctuations and corresponding aquifer response suggests that such intermittent utilization of a slightly larger fraction of the Tehama Formation's large storage capacity during dry years can successfully contribute to meeting the City's water requirements while still accomplishing the management objectives listed above, primarily via corresponding reductions in pumping during normal and wet years.

#### 3.2 PLAN CATEGORIES AND COMPONENTS

To accomplish the BMOs discussed above, this Plan incorporates a number of components that are divided into five categories: 1) monitoring program, 2) water resource sustainability, 3) groundwater resource protection, 4) agency coordination and public outreach, and 5) plan

implementation and updates. Each of these categories and the Plan components within each category are described in this section.

The Plan components reflect the focus on local groundwater management in the Solano Subbasin by the City and continuing cooperation with the members of the SWA and other stakeholders in the Solano Subbasin. In summary, this Plan aids the City in the continued management of its own groundwater resources, and provides the foundation for the City and other entities in the basin to cooperatively manage and potentially expand use of groundwater on a regional basis for municipal and emergency water supply purposes.

#### **Category 1: Monitoring Program**

- 1A. Elements of Monitoring Program
- 1B. Evaluation and Reporting of Monitoring Data

#### Category 2: Water Resource Sustainability

- 2A. Maintaining Stable Groundwater Levels
- 2B. Determination of Sustainable Pumpage
- 2C. Continuation of Conjunctive Use Operations
- 2D. Integration of Recycled Water
- 2E. Water Conservation

#### **Category 3: Groundwater Resource Protection**

- 3A. Well Construction and Destruction Policies
- 3B. Identification and Management of Recharge Areas and Wellhead Protection Areas
- 3C. Management and Mitigation of Contaminated Groundwater
- 3D. Long-Term Salinity Management

#### Category 4: Agency Coordination and Public Outreach

- 4A. Continuation of Local, State, and Federal Agency Relationships
- 4B. Public Outreach
- 4C. Water Awareness Education

#### Category 5: Plan Implementation and Updates

- 5A. Plan Implementation and Reporting
- 5B. Provisions to Update the Groundwater Management Plan

#### 3.3 COMPONENT CATEGORY 1: MONITORING PROGRAM

The City's groundwater monitoring program was initially described in its first *AB 3030 Groundwater Management Plan* (West Yost, 1995), and additions to the monitoring program were outlined in a report updating local groundwater conditions through 2003 (LSCE, 2004b). The City's current groundwater monitoring program includes monitoring of groundwater levels, quality, and production. As discussed below, the City is coordinating with SCWA on the addition of two land subsidence monitoring stations to the regional monitoring program in January 2011.

#### 3.3.1 Component 1A: Elements of Monitoring Program

The City's groundwater monitoring program is summarized in **Table 3-1**, and the monitoring locations are shown on **Figure 3-1**. The monitoring program summarized on this table and figure does not include 14 shallow monitoring wells located at the City's two wastewater treatment plants (WWTPs). There are nine monitoring wells at the Gibson Creek WWTP and five monitoring wells at the Easterly WWTP. Although these wells are not included in the groundwater monitoring program summarized below, the monitoring results are evaluated as part of achieving the third BMO (preservation of groundwater quality).

#### **Groundwater Levels**

As shown in **Table 3-1**, manual water level measurements are currently made by the City on a semi-annual basis in 11 of its 13 production wells and all of its dedicated Tehama Formation monitoring wells. In addition to the manual measurements, nine production wells are equipped with transducers connected to the City's SCADA system. Additional transducers are scheduled to be deployed in wells MW-14, MW15-1815, MW16-1430, MW-98A, and MW-98C in January 2011.

In 1992, the City implemented a program to obtain spring and fall water level measurements from its production wells that best represent static conditions. Manual water level measurements are preceded by a three-day shutdown period for all wells in order to eliminate the most pronounced effects of recent pumping to ensure consistent and generally static monitoring conditions. However, the spring measurements often do not reflect the highest groundwater levels of the year, and the fall measurements provide little indication of the low groundwater levels that occur during the summer. Since 2002, transducer measurements from the City's SCADA system have also been available to indicate the highest water levels in the spring and the lowest water levels during the summer. The SCADA system allows the City to continuously monitor pumpage and water levels in most of its active production wells. The exceptions are Well 1, which has a SCADA connection that monitors pumpage but not water levels, and Wells 2, 3, and DeMello, which are not connected to the SCADA system. Water level readings are taken every 10 seconds in the other wells, and the data are automatically uploaded via radio or telephone line to a computer at the City's Water Treatment Plant on Allison Road.

In 2001, the City began manual water level measurements in monitoring wells completed in all three zones of the Tehama Formation. As summarized in **Table 3-1**, manual water level measurements are currently made semi-annually (spring and fall) in 11 monitoring wells.

Several other entities also monitor groundwater levels in the vicinity of the City, including SCWA, DWR, USBR, SID, and RNVWD. Data collected by DWR and USBR are available on DWR's website, and data collected by SID and RNVWD are available from those districts. SWA also acts as a repository for water level data collected by DWR, USBR, SID, and UCD under the SWA-4 agreement. The purpose of the SWA-4 agreement is to coordinate groundwater monitoring data among the SWA member agencies and also other agencies, including DWR and USBR. SCWA has responsibility for managing the data and preparing periodic reports on behalf

of SWA to summarize the compiled data and describe historical and current groundwater conditions.

SWA has completed an initial report on groundwater conditions in northern Solano County (Summers Engineering, 1995) and three data summary reports, the most recent of which is entitled 2003-2005 Ground Water Report, Groundwater Conditions in Solano County (SWA, in progress). This report lists the wells with groundwater data, shows the sampling frequency, and refers to a database that includes the well construction and water level data. The report includes data for 139 to 202 wells, depending of the year water levels were measured. The majority of these wells are monitored monthly or semi-annually; some wells are monitored annually. The majority of these wells are agricultural or domestic wells perforated in the upper aquifers (above 400 feet).

The regional groundwater monitoring program has been expanded. In October 2007, SCWA began installing multiple-completion monitoring wells at four locations in northern Solano County. Since then, monitoring wells have been installed at all four locations and are currently equipped with transducers. Transducer data are downloaded and analyzed at least semi-annually. Manual water level measurements are taken on the same frequency. A summary of construction information and monitoring activities for each SCWA monitoring well is provided in **Table 3-2**.

#### **Groundwater Quality**

Groundwater quality sampling of the City's production wells for general minerals, inorganics, and organics is conducted every three years as required for all public water supply systems. The City also collects samples annually for nitrate analysis. Samples were collected quarterly for radionuclide analysis from May 2005 to January 2006, and the City has received a 9-year waiver from the California Department of Public Health (DPH) for future radionuclide sampling because the gross alpha results were below the threshold of 3 pCi/L. The City's current groundwater quality monitoring program is summarized in **Table 3-1**.

SWA does not include groundwater quality data in its periodic monitoring reports; therefore, there is no central repository for water quality data in Solano County. In the vicinity of the City, RNVWD and SID conduct routine groundwater quality sampling. Although RNVWD has two production wells, only one is operated for public water supply. Due to elevated arsenic concentrations, exceeding the MCL of 10 ug/L, in the second production well, it is currently offline. Routine water quality sampling is conducted in both wells as required by DPH.

SID's SB 1938 Groundwater Management Plan Upgrade (Summers Engineering, 2006) states that groundwater quality is monitored on a rotating basis in agricultural wells in the SID service area. Although the number of wells sampled each year and the sample analyses conducted are not specified, SID produces a brief annual report each year that includes groundwater quality results. The 2009 annual report shows that four wells were sampled, and the samples were analyzed for general minerals including nitrate, boron, and sodium adsorption ratio (SAR). The 2009 annual report also indicates that nine SID wells have been sampled since 2001, and most of these were sampled every other year (Summers Engineering, 2009).

#### **Groundwater Production**

The City monitors pumpage in its water supply wells on a daily basis. As shown in **Table 3-1**, all but three water supply wells are connected to the SCADA system that allows the City to monitor pumpage electronically. By February of 2011, Wells 2 and 3 will be added to the SCADA system, leaving only the inactive DeMello Well to be monitored manually. The electronic pumpage data are typically recorded daily (at noon), but more frequent data can be collected if necessary. Other well information such as flow rate, pressure, pump speed, chemical tank level, etc. are also recorded daily.

There is no regional compilation of pumpage data in Solano County because SWA does not include pumpage in its database or reports. In the vicinity of the City, municipal pumpage is monitored by RNVWD. SID monitors agricultural pumpage from District wells but does not monitor non-District pumpage within its boundaries. As noted above, the DeMello well has been offline since 2005.

#### Land Subsidence

The City does not currently monitor land subsidence within its boundaries, and regional monitoring of land subsidence in Solano County has been limited. Regional land subsidence monitoring has included non-instrumented GPS monuments and continuous GPS monitoring stations; there are no extensometers in Solano County. In January 2011, two permanent GPS subsidence stations (located at the Vacaville Well 16 and SCWA Dixon monitoring well sites) will be added to the regional monitoring network.

The Sacramento-San Joaquin Delta non-instrumented GPS network consists of about 120 monuments, including about 30 monuments in Solano County. This network was initially surveyed in 1997 and resurveyed in 2002, but funding has not been available to process the data from the 2002 resurvey. Yolo County also has a non-instrumented GPS monitoring network consisting of 58 stations. The Yolo County network was surveyed in 1999, 2002, and 2005. The 2005 survey of the Yolo County network included several stations in northern Solano County. GPS monitoring locations in northern Solano County and adjoining portions of Yolo County are shown on **Figure 2-9**.

Instrumented GPS monitoring stations are generally referred to as Continuously Operating Reference Stations (CORS). Each CORS site includes a high-resolution GPS receiver and antenna with a solar collector and battery for power supply. The GPS receivers are attached to steel or concrete structures that are anchored deep into the soil. GPS positions are recorded at intervals of five to 30 seconds, and a daily average is calculated from all of the data to achieve maximum accuracy. CORS sites use some form of telemetry (typically a radio transceiver) to upload the data. After processing, the data are accessible on Internet sites operated by entities such as the National Geodetic Survey (NGS) or the California Spatial Reference Center (CSRC).

At present, there is one CORS site in northern Solano County. This site, labeled P267, is located south of Dixon and approximately six miles east of the City (**Figure 2-9**) and is operated by the Plate Boundary Observatory. Historical data are limited for this station, which began operation in

April 2005. The two new subsidence stations scheduled for January of 2011 will also be operated by the Plate Boundary Observatory.

#### Surface Water Flows and Quality

Monitoring of surface water flows and quality is generally not applicable to the City of Vacaville for three reasons: 1) there are no major streams in the vicinity of the City, 2) the City's production wells are completed in relatively deep and confined zones of the Tehama Formation (primarily the basal zone), and 3) there is no direct interaction between groundwater in this zone and surface water.

As required by DPH, the City monitors the quality of surface water delivered by the Solano Project and the SWP on a quarterly basis. Both raw and treated surface water are sampled at the City's water treatment plant and analyzed for nitrate on a quarterly basis (except for the first quarter) and for general mineral, general physical, inorganic, and organic constituents annually.

#### **Actions**

- Continue the City's existing groundwater monitoring program and complement with information gathered by other local and state agencies (e.g., DWR, SID, and USBR).
- Expand regional groundwater monitoring programs to ensure effective groundwater resource management and accomplishment of the BMOs.
  - o Coordinate with SCWA regarding the adequacy of regional groundwater monitoring networks and programs.
  - Coordinate with SCWA on planned construction of additional monitoring facilities in northern Solano County.
  - o Coordinate with SCWA on implementation of a land subsidence monitoring program.

#### 3.3.2 Component 1B: Evaluation and Reporting of Monitoring Data

Groundwater level, quality, and production data collected as part of the City's monitoring program are periodically entered into a database, which allows the data to be summarized on tables and plots in an efficient manner. The data are routinely reviewed to check for any significant changes in groundwater conditions. On a less frequent basis, the data are comprehensively evaluated and a report is prepared to summarize the data.

The most recent evaluation of groundwater conditions in the Vacaville area is presented in the report entitled *Hydrostratigraphic Interpretation and Groundwater Conditions of the Northern Solano County Deep Aquifer System*, (LSCE, 2010). Previous reports have been prepared at least every other year beginning in 2000. Most of these reports have been comprehensive, detailed reports that contain much more analysis than is generally required in a routine annual summary of the data. Such routine annual reporting is recommended in the future, as described below.

#### **Actions**

- Prepare a brief annual summary of groundwater and land subsidence data collected through spring (i.e., March or April) in a groundwater management report to be completed each year by August 1<sup>st</sup>.
- Coordinate with SWA-4 on the maintenance and utilization of the regional monitoring database, including regular transfer of City data and coordination with others on the use of the data to assess basin conditions relative to the BMOs. Additionally, coordinate with SWA-4 on monitoring protocols (such as groundwater level objectives) being used to assess the effect of pumpage on levels and achieving BMOs.
- Coordinate with SWA-4 regarding the adequacy of regional evaluation and reporting of groundwater data. Potential improvements to the SWA database and reports include:
  - o the addition of the City's wells and water level data;
  - o the addition of groundwater quality, pumpage, and land subsidence data;
  - o preparing reports on an annual basis to summarize data collected during the previous year; and
  - o preparing a coordinated update of groundwater conditions in the subbasin at least every five years.

#### 3.4 COMPONENT CATEGORY 2: WATER RESOURCE SUSTAINABILITY

#### 3.4.1 Component 2A: Maintaining Stable Groundwater Levels

Accomplishment of the second BMO (avoidance of progressive groundwater level declines) requires that generally stable groundwater levels be maintained in the Tehama Formation, especially in the basal zone. On a subbasin scale, there have been increases in groundwater levels and storage since the Solano Project began delivering water in the late 1950s. As described above, however, groundwater levels in the basal zone of the Tehama Formation continue to exhibit a localized cone of depression in the vicinity of the City's Elmira Road well field, and groundwater levels in this area have fluctuated directly in response to the amount of pumpage. Following several years of maintaining total annual pumpage at 6,600 to 6,700 AF, basal zone groundwater levels in the Elmira Road wells appear to have stabilized as of spring 2006. Since 2007, reduced groundwater pumping by the City has caused groundwater levels in the basal aquifer to rebound significantly (upwards of 25 feet in some areas).

Water level fluctuations in the basal zone are typical of conditions in an area where groundwater and surface water are conjunctively managed. Historically, more groundwater was pumped from storage during dry years, and that storage was replenished when pumpage was reduced during subsequent wet years. Annual pumpage was held constant from 2002 to 2007 to observe water level responses in the basal zone. As discussed above, the City's conjunctive water management program allows it to adjust its groundwater production so that groundwater levels recover to spring 1992-1993 "base year" levels during normal years. The base year water levels are used to define the "normal condition" referenced in the Master Water Agreement (SID and City, 1995). Groundwater levels may decline below base year levels during dry years with increased

26

pumpage, but levels should remain above historical lows. Conjunctive water management is again used to restore groundwater levels to base year conditions following a dry year when increased pumpage has occurred.

In recent years, the City has also managed the location of its groundwater extraction in an effort to shift pumpage away from the Elmira Road well field to the northeast sector of the City. Prior to the construction of City wells 14, 15, and 16 in the northeast sector, there was no significant groundwater development of the basal zone of the Tehama Formation for municipal water supply in this area, although a small amount of groundwater is known to be produced from this zone for commercial purposes. Somewhat further north, there is a small amount of groundwater development from this zone by RNVWD. The City plans to develop some additional groundwater to supplement its currently available groundwater and surface water resources and add that yield to the existing water supply. One area identified for potential future groundwater development is in the northeast sector.

#### **Actions**

- Continue to manage groundwater and surface water conjunctively to ensure that groundwater levels in the Elmira Road wells recover to spring 1992-1993 "base year" levels during normal years based on the following criteria:
  - O During dry years with increased pumpage, recognize that groundwater levels may decline below base year levels but maintain groundwater levels above historical lows.
  - Use conjunctive water management to restore groundwater levels to base year conditions following a dry year when increased pumpage has occurred.
  - Use 1992-1993 base year groundwater levels, in conjunction with the more complete data from 2002-2003, to measure aquifer system response to pumping and assess the sustainable pumpage.
- Manage pumping away from Elmira Road to prevent progressive groundwater level declines in other areas.
- Continue groundwater development programs that help to achieve the BMOs by optimizing the pumping distribution in the City's urban planning area.

#### 3.4.2 Component 2B: Determination of Sustainable Pumpage

In order to accomplish BMOs that pertain to groundwater in the Vacaville area, it will be important to determine what yield can be developed on both a regular and an intermittent (dry period or emergency) basis. A determination of sustainable pumpage, particularly for the basal zone of the Tehama Formation, will be required to accomplish the main objectives of operating within the yield of the groundwater basin and avoiding overdraft.

The intent of this Plan component is to develop further understanding and quantification of sustainable pumpage from the Tehama Formation (especially the basal zone), accounting for variations in hydrologic conditions and the location and amount of pumpage, so that groundwater

development and use can be managed in such a way to meet an appropriate fraction of total water demand while avoiding over pumping that could result in overdraft conditions.

In the future, in coordination with other SWA members and state and federal agencies, implementation of this Plan component will be important in accomplishing the first and second management objectives for the basin. The observation of historical groundwater conditions, in combination with knowledge of pumpage from the basal zone of the Tehama Formation, has led to the City's current operational practices as well as general expectations regarding the approximate yield of this aquifer in the vicinity of the City. Historical operating experience, complemented by observed groundwater conditions, is an appropriate basis to initially determine available groundwater supplies. However, it is possible and appropriate to more precisely analyze the basin to determine values or ranges of yield under varying hydrologic conditions, and to assess the impacts of various management actions that might be implemented in the basin. Previous reports, including LSCE (2010), include recommendations for the future development of a numerical groundwater flow model that could be utilized for determination of the yield of the subbasin under existing land use and groundwater and surface water development conditions. Such a model could also be used for implementation of this Plan component to assess the yield of the subbasin under future land use conditions as well as future ranges of surface water importation, groundwater development, and recycled water use through varying hydrologic conditions, i.e., wet and dry periods that affect the availability of imported surface water.

#### **Actions**

- Assess levels of pumpage relative to the sustainable yield of the principal aquifer system.
  - Update sustainable pumpage estimates with expanded monitoring data (e.g., monitoring conducted with the new SCWA monitoring wells installed at the periphery of the urban planning area).
- Refine assessment of hydrogeologic conditions and the conceptual model in preparation for the future development of a regional numerical groundwater flow model.
  - o Improve groundwater extraction (non-City pumpage) and recharge estimates.
  - o Refine conceptual model of subbasin (e.g., conceptual model for enlarged study area).
  - o Investigate stream-aquifer interactions.
- Discuss joint development of a regional numerical groundwater flow model to simulate and evaluate future water resources management scenarios with SWA and other entities that overlie the subbasin.

#### 3.4.3 Component 2C: Continuation of Conjunctive Use Operations

The City conjunctively manages its groundwater and surface water resources to most effectively use those resources during different water year types. This has been previously demonstrated to be an effective and flexible management approach. Conjunctive water management goals have been established particularly to accomplish the second BMO, i.e., avoidance of progressive groundwater level declines. Continuation of conjunctive water management is expected to enable

the City to meet its future water demands to a 20-year horizon and beyond. Groundwater-related objectives of the conjunctive water management program are to:

- Recognize and implement actions to prevent persistent groundwater level declines.
- Continue to maintain groundwater levels above historical lows when levels temporarily
  decline during dry years in order to minimize subsidence and other adverse consequences
  caused by over pumping of the aquifer system.

Planning for additional groundwater development has preliminarily involved the use of an analytical groundwater flow model (LSCE, 2003 and 2007). Monitoring data have been and will continue to be utilized to assess actual response to pumping (particularly within the basal zone) so that operations can be adjusted as necessary to achieve this BMO, i.e. avoidance of progressive groundwater level declines.

As part of the conjunctive management of surface water and groundwater to meet the City's requirements, it is recognized that there will be variations in the amount of available surface water supplies from year to year, particularly since a large fraction of the supply is imported from outside the subbasin. Similarly, there are expected to be variations in groundwater conditions as a function of the local hydrogeology that affect, among other things, the natural recharge to the groundwater basin from year to year. Local hydrology, which affects local groundwater conditions in the basal zone, may be considerably different from the hydrology in a distant (Central Sierra Nevada) location that directly affects the availability of imported surface water in any given year.

Recharge to the basal zone is expected to occur primarily east of the English Hills and north of the Vacaville area where the Tehama Formation outcrops. A significant portion of the recharge is probably the result of leakage from the overlying Quaternary alluvium and the upper zone of the Tehama Formation in the outcrop areas (**Figure 2-5**). Thus, conjunctive water management by the City necessitates particular attention to groundwater level recovery from year to year to ensure that water levels in the basal zone are maintained to meet a regular component of the City's water supply in normal and wet years and a larger component of the water supply during "dry periods" that affect supplemental surface water availability. In light of all the preceding, continuation of this Plan component is essential to accomplishing all the BMOs.

#### **Actions**

- Continue the City's conjunctive management of its available water resources;
- Coordinate with other SWA members to explore other conjunctive use opportunities directed toward the BMOs.

#### 3.4.4 Component 2D: Water Conservation

The City of Vacaville is committed to implementing water conservation programs. The 2005 UWMP contains descriptions of the conservation measures that the City has implemented, plans to implement, or intends to study (Nolte, 2005). This section highlights those measures that are the same as the best management practices (BMPs) outlined by the California Urban Water

Conservation Council. For more than 18 years, the City has participated in a Water Conservation Council that includes other cities in Solano County and SCWA, the City's wholesale supplier of imported surface water. Through regional partnering efforts, the cities have shared resources and benefited from each other's programs and studies.

Water conservation and related public education measures have generally been developed in California to achieve the following goals:

- meet legal mandates,
- reduce average annual potable water demands,
- reduce sewer flows,
- reduce water demands during peak seasons, and
- meet drought restrictions.

The City has implemented the following BMPs to increase water conservation:

- distribution system water audits and leak detection and repair;
- public information;
- school education;
- conservation pricing;
- conservation coordinator;
- residential plumbing retrofits;
- metering with commodity rates for all new connections and retrofit of existing connections;
- large landscape conservation programs and incentives;
- conservation programs for commercial, industrial, and institutional accounts; and
- water waste prohibition.

The City's water conservation and public education program will expand to include the following BMPs found to be locally cost-effective, as detailed in the 2005 UWMP. These BMPs are intended to reduce California's long-term urban water demands and have been incorporated into the water demand management measures section of the Urban Water Management Planning Act.

- Water survey programs for single-family residential and multi-family residential programs (surveys of customers having the greatest potential to reduce water use started in 2006);
- High-efficiency washing machine rebate programs (the City supports the rebate program offered by Pacific Gas & Electric Company); and
- Residential ultra-low-flow toilet replacement program (the City exempted itself from this water demand management measure in its 1999 Water Management Plan; however, it is continuing to research an effective and efficient method to implement in the future).

The City uses a variety of communication tools to encourage water conservation. These tools include: press announcements and newspaper advertisements; public workshops; City web site posting with a dedicated water conservation section to promote water conservation practices and water rate information; billing software that shows each customer's water use over the last 12 months; cooperative exhibits, demonstration sites, library displays, and a water model used for

public meetings and school education; public information through regional projects; speakers for community groups and the media; and coordination with other government agencies, industry groups, public interest groups, and the media.

This Plan component will be incorporated with educational and outreach material to complement other Plan components. This update of the City's Plan includes continuation of public water awareness programs directed toward achievement of the BMOs.

#### **Actions**

• Continue to implement and promote water conservation programs within the City's service area.

#### 3.5 COMPONENT CATEGORY 3: GROUNDWATER RESOURCE PROTECTION

#### 3.5.1 Component 3A: Well Construction and Destruction Policies

Most of the City's groundwater supply is developed from the basal zone of the Tehama Formation. The City's wells are commonly completed to depths of over 600 feet, including many wells over 1,000 feet deep and one well over 1,800 feet deep. Proper well design and construction is required to prevent the movement of poorer quality water between aquifers through the well structure. In coordination with SWA, the City has implemented well construction guidelines to minimize the potential for groundwater quality degradation in deeper aquifers. These guidelines, which especially include the installation of deep seals, are followed for construction of all new City wells. The City also continues to follow the Solano County Code (see below) and guidance provided in DWR Bulletins 74-81 and 74-90 on well construction (DWR, 1981 and 1990).

The Solano County Environmental Health Services Division of the Department of Resource Management is responsible for well construction permitting in Solano County. The County Code, Chapter 13.10, effectively implements the State Well Standards for water supply wells, monitoring wells, and cathodic protection wells. Permitting of municipal supply wells is also within the purview of DPH. The third BMO, preservation of groundwater quality, requires that all wells be properly constructed and maintained during their operational lives and properly destroyed after their useful lives, so that they do not adversely affect groundwater quality by, for example, serving as conduits for movement of contaminants from the ground surface and/or from an aquifer with poor groundwater quality to one with good quality. Toward that end, this component is included in the overall plan to support well construction and destruction policies, and to participate in their implementation in the subbasin, particularly with regard to surface and inter-aquifer well sealing and proper well destruction, which are critical in the management of a multiple aquifer system.

#### **Actions**

• Continue current well construction and destruction policies.

• Coordinate with other SWA members as appropriate on well construction and future resource utilization.

### 3.5.2 Component 3B: Identification and Management of Recharge Areas and Wellhead Protection Areas

The 1986 Amendments to the federal Safe Drinking Water Act (SDWA) established requirements for new Wellhead Protection Programs (WPPs) to protect groundwater that supplies drinking water wells for public water systems. Each state was required to prepare a WPP and submit it to the USEPA by June 19, 1989. However, California did not develop an active statewide WPP at that time. Subsequently, in 1996, reauthorization of the SDWA established a related program called the Source Water Assessment Program. In 1999, the DPH Division of Drinking Water and Environmental Management developed its Drinking Water Source Assessment Program (DWSAP), which was approved by USEPA. The overall objective of the DWSAP is to ensure that the quality of drinking water sources is protected. The wellhead protection aspect of this groundwater management plan component is now essentially required as a result of the 1996 SDWA reauthorization.

In California, the DWSAP satisfies the mandates of both the 1986 and 1996 SDWA amendments. The California DWSAP includes delineation of Groundwater Protection Zones surrounding an existing or proposed drinking water source where contaminants have the potential to migrate and reach that source. The program includes preparation of an inventory of activities that may lead to the release of contaminants within these zones. The activities, referred to in the DWSAP as Potentially Contaminating Activities, include such land uses as gas stations and dry cleaners, as well as many other land uses. Known contaminant plumes regulated by local, state, and federal agencies are also included. The Groundwater Protection Zones, which are determined based on local hydrogeological conditions and also well operation and construction parameters, represent the approximate area from which groundwater would be withdrawn during 2, 5, and 10-year time periods. These zones also represent the area in which contaminants released to groundwater could migrate and potentially affect the groundwater extracted by wells located within the designated zones. The DWSAP evaluation also includes a risk or vulnerability ranking based on a combined numerical score that results from points assigned to various evaluations conducted as part of the DWSAP process. This ranking provides a relative indication of the potential susceptibility of drinking water sources to contamination.

DPH is responsible for conducting DWSAP assessments for systems existing prior to the adoption of the California program but has encouraged purveyors to perform their own assessments. Assessments for existing systems were due to be completed by May 2003.

Permitting of a new water supply well requires that the applicant complete a DWSAP analysis as part of the permit process. Fifteen DWSAP assessments have been completed on behalf of the City. The results of the DWSAP assessments can be used as a planning tool to guide land use development in the vicinity of water sources. The DWSAP analyses prepared for water sources in the basin should, in some fashion, be reviewed at least every five years and updated as appropriate. The collective DWSAP information can also be integrated with other management

activities, including siting of new wells, land use policies, and the County's Code concerning well construction.

This Plan component is included to incorporate the DWSAP efforts into the City's Groundwater Management Plan. Compliance with these DPH requirements is a key part of accomplishing the BMOs.

#### **Actions**

- Employ wellhead protection measures to ensure long-term sustainability of good quality water.
  - o Use DWSAP information, including delineation of source area and protection zones.
  - o Require deep sanitary seal construction standards for municipal supply wells.
  - o Employ well destruction policy to prevent groundwater contamination.
- Coordinate with other SWA members (as applicable) regarding DWSAP analyses (and also other environmental assessments) conducted to help guide management decisions in the subbasin.
- Promote recharge area protection to mitigate impacts of urban infrastructure and sources of groundwater contamination that could reduce recharge potential.

#### 3.5.3 Component 3C: Management and Mitigation of Contaminated Groundwater

In general, groundwater is of high quality and meets drinking water standards in the Vacaville area.

In the more publicized arena of hazardous chemical contamination that falls under the purview of the Regional Water Quality Control Board and sometimes other state or federal agencies, there have been localized instances of impacts on groundwater quality; however, these do not constrain existing or potential municipal supplies. This Plan includes active monitoring of groundwater quality and active participation with local health and other agencies as appropriate to identify spills, leaks or other threats to groundwater quality, and to participate in their control and cleanup such that groundwater quality is not impacted and does not limit water supply. Mitigation measures will be employed (well construction, placement, treatment, etc.) as an element of developing groundwater supplies in order to reduce nitrate concentrations and other constituent concentrations if they exceed drinking water standards, as necessary.

When groundwater remediation activities involve groundwater extraction, remediated groundwater may be discharged to Publicly Owned Treatment Works (POTW) with permitting authority through the POTW program and the appropriate regulatory agency approvals, including the Regional Water Quality Control Board and the State Water Resources Control Board. Remediated groundwater may also be discharged to surface water, applied to land, recycled, or otherwise beneficially used or discharged, with all required agency approvals and permits.

The Solano County Environmental Health Services Division has local oversight for groundwater protection through the Underground Storage Tank (UST) and Hazardous Materials programs. The UST regulations provide groundwater protection through annual integrity testing and stringent tank requirements.

Prevention is the most important factor in minimizing groundwater contamination. The City promotes public awareness of the importance of preventing water pollution through its web site and other outreach tools.

#### **Actions**

- Identify short and longer-term water quality trends and actions needed to sustain a supply of good quality groundwater.
- Employ BMPs to limit potential sources of contamination in the environment.
- Coordinate with the County Environmental Health Services Division and other land use/regulatory agencies to develop a method for identifying contamination concerns and mitigating public water supply contamination.
  - o Identify locations of point sources of contamination.
  - o Identify major nonpoint sources of contamination.
  - Mitigate potential impacts on groundwater quality resulting from point or nonpoint sources of contamination.
  - o Identify short and longer-term water quality trends and actions needed to sustain a supply of good quality groundwater.
- Coordinate with other SWA members and the County Environmental Health Services Division to assess the quality of groundwater used by private well owners in the subbasin.

#### 3.5.4 Component 3D: Long-Term Salinity Management Programs

In general, groundwater quality in the Solano Subbasin is such that groundwater supplies meet standards for beneficial uses in the basin, which include primarily Municipal and Domestic Supply and Agricultural Supply. There also have been no notable historical trends of groundwater quality degradation in the Solano Subbasin over time. However, several factors suggest that observations and interpretation of groundwater quality warrant attention to ensure long-term preservation of groundwater quality. Notable among these factors are: 1) historical and current agricultural irrigation practices, 2) other historical and current land uses that have contributed or can contribute higher salt concentrations than other sources of water supply in the basin (including, but not limited to, water softeners), 3) the presence of high water tables which cause increased soil salinity due to evaporation in some areas, and 4) tidal influences in the Sacramento-San Joaquin Delta. The combination of these factors suggests that, on a long-term basis, there could be an accumulation of dissolved minerals in the aquifer system if salinity is not managed in a way to avoid undesirable groundwater quality degradation. Consequently, this component is included in the overall Groundwater Management Plan to include the interpretation

of groundwater quality data and to incorporate groundwater quality as an important consideration in the implementation of the other Plan components, most notably continuation of conjunctive use operations, integration of recycled water, and management and mitigation of contaminated groundwater. The long-term salinity management component is essential to accomplishing the third management objective of preserving groundwater quality in the basin.

#### **Actions**

• Implement measures to avoid salt accumulation and other adverse changes in groundwater chemistry in the subbasin.

### 3.6 COMPONENT CATEGORY 4: AGENCY COORDINATION AND PUBLIC OUTREACH

## 3.6.1 Component 4A: Continuation of Local, State, and Federal Agency Relationships

The City has long-established working relationships with local and state agencies that will continue on an ongoing basis. The City will continue to interact with state agencies, particularly DWR, on the operation of the SWP and the agreement with DWR for Settlement water. The availability of surface water resources is key to continued conjunctive use operations in the future. The City has a historical and ongoing working relationship with local agencies, as well as with other local groundwater pumpers, to manage supplies to effectively meet water demands within the available yields of imported surface water and local groundwater.

The joint powers authority process that led to the formation of the SWA is a classic illustration of local agency partnering that has produced the beginnings of integrated regional water resources management. As a result of the willingness of the SWA members to seek opportunities to work together and develop programs that mutually benefit the region as well as their individual communities, these agencies prepared and executed the SWA-4 Project that initiated a collaborative and integrated approach to several of the aspects of groundwater resource management that are now included in this Plan. As a result of the SWA-4 Project, the member agencies have the capability to integrate their database management efforts, develop a regional monitoring network, and prepare reports on groundwater conditions in the subbasin.

In 2004 and 2005, SCWA coordinated meetings and other exchanges between local agencies (including the City, SID, MPWD, and RD 2068) with adopted groundwater management plans. The purpose was to identify common elements that could be used by each agency to update its individual plan to be consistent with the amended Water Code. Periodic review and update of the plans is planned to be coordinated with the SCWA member agencies.

The SWA-4 members are especially engaged in collaborative activities that are directed toward an integrated regional approach to groundwater resources management. The SWA-4 members also have the opportunity to inform citizens in their service areas of groundwater management activities, including plan updates and opportunities for the public to attend meetings and/or

35

provide comments on any issues of concern regarding groundwater in the northern Solano County area.

In 2005, SCWA adopted an IRWMP, which identifies and prioritizes water related actions for the Solano County agencies, including the City. One of the highest priorities of the IRWMP is continuation of conjunctive use and associated groundwater management. This Plan component is included to formalize the historical local and state agency working relationships as part of comprehensively managing local groundwater, in concert with imported surface water and local recycled water, to accomplish all the management objectives for the basin.

#### **Actions**

- Continue to develop working relationships with local, state, and federal agencies (regulatory and other) to achieve broader local and regional benefits.
- Continue to pursue grant opportunities in cooperation with SCWA to fund basin management
  activities and regional water projects including the planned IRWMP for the Westside
  Subregion that encompasses Solano County and other counties.

#### 3.6.2 Component 4B: Public Outreach

The purpose of the Plan is to maintain a high quality, reliable, and sustainable water supply for the citizens of Vacaville. To accomplish this, the Plan components describe how the City intends to manage its water resources in support of four principle BMOs directed toward the sustainability of groundwater supplies. As the City is managing its water resources as a service to the local citizenry, the City is committed to engaging the public in awareness of the Plan's purpose and objectives.

The City plans to promote public awareness of the Plan through printed media, including bill inserts and periodic news releases.

#### **Actions**

- Continue public involvement process through the use of City Council meetings that periodically include updates on water resources management activities by the City.
- Continue public outreach through the use of the City's web site, bill inserts, radio spots, and printed media. These notices will include contact information so that interested parties can request additional information, ask questions, or provide comments on water resources management activities.

#### 3.6.3 Component 4C: Water Awareness Education

The City of Vacaville is committed to implementing water awareness and conservation programs. The UWMP contains descriptions of the measures that the City has implemented, plans to implement, or intends to study (Nolte, 2005).

The City uses a variety of communication tools to provide for public information and involvement. These tools include: press announcements and newspaper advertisements; radio spots; public workshops; City web site posting with a dedicated water conservation section to promote water conservation practices and water rate information; billing software that shows each customer's water use over the last 12 months; cooperative exhibits, demonstration sites, library displays, and a water model used for public meetings and school education; public information through regional projects; speakers for community groups and the media; and coordination with other government agencies, industry groups, public interest groups, and the media.

This Plan component will be incorporated with educational and outreach materials to complement other Plan components, including the Water Conservation component. This update of the City's Plan will continue to include public education and water awareness programs directed toward achievement of the four BMOs.

#### **Actions**

• Continue water awareness education programs.

#### 3.7 COMPONENT CATEGORY 5: PLAN IMPLEMENTATION AND UPDATES

#### 3.7.1 Component 5A: Plan Implementation and Reporting

#### Action Plan

**Table 3-3** summarizes the action items discussed under each Plan component and the implementation schedule for each item. Action items planned to be completed within two years are labeled "short-term" actions, and items expected to require more than two years to complete are labeled "long-term" actions. Action items that represent on-going groundwater management activities conducted by the City are labeled "continuing" actions.

#### Provisions to Cooperate with Other Agencies

The IRWMP adopted by SCWA in 2005 identifies and prioritizes regional water-related actions for the Solano County agencies, including the City. Highest priority actions identified in the IRWMP include quantifying countywide water demand and supply, increasing opportunities for conjunctive use, increasing the use of groundwater as part of conjunctive use operations, and implementation of water use efficiency programs (CDM, 2005). The City supports implementation of the current IRWMP and also efforts to develop a new IRWMP for the Westside Subregion.

As a member of the SWA-4 Project, the City will update other members on its groundwater monitoring and management activities. Updates to SWA-4 members include information and data transfer via reports and data exchanges as further described below.

#### **Groundwater Management Reports**

As described in the Introduction to this Plan, local groundwater management planning already includes, among several other activities, analysis of groundwater conditions and preparation of periodic reports on groundwater and all other aspects of water resources and water supplies within the Solano Subbasin in the vicinity of the City of Vacaville. In addition, the City updated its UWMP (Nolte, 2005) in 2005 and finalized a comprehensive report on groundwater conditions, including recommendations for additional groundwater and subsidence monitoring (LSCE, 2010).

Beginning in the 1980s, the City has prepared several reports to describe its groundwater utilization and summarize groundwater level and quality trends. The City plans to produce future reports on an annual basis to describe the status of management actions performed and/or recommended, including monitoring–related and other cooperative activities with other Solano County entities or state or federal agencies. These annual reports will include summaries of monitoring data collected during the previous year, including groundwater conditions (groundwater levels, quality, and production) and land subsidence data. The reports will include data collected through spring (March 31<sup>st</sup>) so that water level recovery during the winter months can be evaluated. The reports will also summarize current water requirements, use of local groundwater and imported surface water from the Solano Project and the SWP to meet those requirements, and other appropriate details about water requirements and supplies such as, for example, the status of introducing recycled water as a component of non-potable water supply. As appropriate, other more detailed technical reports on various aspects of Plan implementation and reports prepared in coordination with others, such as SCWA and/or SWA, would complement the City's annual management reports.

#### **Actions**

- Cooperate with other agencies.
  - o Provide copies of adopted Plan, and related reports, to SCWA/SWA members.
  - o Support the IRWMP, including implementation of priority objectives of the IRWMP.
- Prepare groundwater management reports.
  - Prepare annual groundwater management reports to be completed by August 1<sup>st</sup>.
     Reports will summarize activities conducted by the City to implement the components of the Plan and will include a summary of monitoring data collected through spring (March 31<sup>st</sup>).
  - Coordinate with SWA to prepare an update of groundwater conditions in the subbasin every five years.

#### 3.7.2 Component 5B: Provisions to Update the Groundwater Management Plan

The components of this Plan reflect the current understanding of the occurrence of groundwater in the Solano Subbasin in the vicinity of Vacaville and specific problems or areas of concern about that resource. The Plan components are designed to achieve specified objectives to utilize local groundwater for regular water supply while both protecting and preserving groundwater quantity and quality. While the Plan provides a framework for present and future actions, new data will be developed as a result of Plan implementation. That new data could identify conditions which will require modifications to currently definable management actions. As a result, this Plan is intended to be a flexible document that can be updated to modify existing components and/or incorporate new components as appropriate in order to recognize and respond to future groundwater conditions. Review and update of this Plan would initially occur in about five years, or sooner if necessary. Subsequent future updates would be similarly scheduled. SWA members would be apprised of future updates to the City's Plan to ensure that the City's Plan is consistent with BMOs and management actions being implemented by others utilizing water resources within the same basin/subbasin. The City will also conduct outreach to encourage public participation in future Plan updates.

#### **Actions**

Review and update Plan every five years or more often as needed.

#### 4.0 REFERENCES

- Blodgett, J.C., M.E. Ikehara, and G.E. Williams. 1990. *Monitoring Land Subsidence in Sacramento Valley, California Using GPS*. Journal of Surveying Engineering. v. 116, no. 2.
- California Department of Water Resources. 1981. Water Well Standards: State of California. Bulletin 74-81. Sacramento, CA.
- California Department of Water Resources. 1990. California Well Standards; Water Wells, Monitoring Wells, Cathodic Protection Wells. Bulletin 74-90. Sacramento, CA.
- California Department of Water Resources. 2003a. *Draft Guidebook for Implementation of Senate Bill 610 and Senate Bill 221 of 2001*. Sacramento, CA.
- California Department of Water Resources. 2003b. *California's Groundwater, Bulletin 118 Update 2003*. Sacramento, CA.
- California Department of Water Resources. 2010. *Groundwater Basin Maps and Descriptions*. Available: <a href="http://www.groundwater.water.ca.gov/bulletin118/basin\_desc/">http://www.groundwater.water.ca.gov/bulletin118/basin\_desc/</a>. Accessed December 2010. Solano Subbasin last updates February 27, 2004.
- Carollo Engineers. 2003. *City of Vacaville Recycled Water Master Plan (Draft)*. Prepared for City of Vacaville. Sacramento, CA
- Dixon, City of. 2008. City of Dixon General Plan Update, Background Report.
- Hantush, M.S. and C.E. Jacob. 1955. *Non-Steady Radial Flow in an Infinite Leaky Aquifer*. American Geophysical Union Transactions. v. 36, p. 95-100.
- Helley, E.J. and R.W. Graymer. 1997. *Quaternary geology of Contra Costa, and surrounding parts of Alameda, Marin, Sonoma, Solano, Sacramento, and San Joaquin Counties, California*: a digital database: U.S. Geological Survey Open-File Report 97-98, 2 sheets (plot files), scale 1:100,000, 20p., 28 Arc/Info coverage's. Available: <a href="http://geopubs.wr.usgs.gov/open-file/of97-98">http://geopubs.wr.usgs.gov/open-file/of97-98</a>.
- Ikehara, M.E. 1994. *Global positioning system surveying to monitor land subsidence in the Sacramento Valley, California, USA*. Hydrological Sciences Journal 39(5):417-429.
- Knudsen, K.L., J.M. Sowers, R.C. Witter, C.M. Wentworth, E.J. Helley, R.S. Nicholson, H.M. Wright, and K.M. Brown. 2000. Preliminary maps of Quaternary deposits and liquifaction susceptibility, nine-county San Francisco Bay region, California: U.S. Geological Survey Open-File Report 00-444, 2 sheets, scale 1:275,000, 3 Arc/Info databases. Available: <a href="http://geopubs.wr.usgs.gov/open-file/of00-444">http://geopubs.wr.usgs.gov/open-file/of00-444</a>.

- Luhdorff and Scalmanini, Consulting Engineers. 2003a. *City of Vacaville AB 3030 Management Plan Update Through 2002*. Prepared for City of Vacaville. Woodland, CA.
- Luhdorff and Scalmanini, Consulting Engineers. 2003b. *City of Vacaville SB 610 Water Supply Assessment, Groundwater Source Sufficiency*. Prepared for City of Vacaville. Woodland, CA.
- Luhdorff and Scalmanini, Consulting Engineers. 2004a. *Groundwater Monitoring Program,*Data Management System, and Update of Groundwater Conditions in the Yolo County

  Area. Prepared for Yolo County Flood Control and Water Conservation District.

  Woodland, CA.
- Luhdorff and Scalmanini, Consulting Engineers. 2004b. City of Vacaville Groundwater Monitoring and AB 3030 Management Program, Update of Groundwater Conditions through 2003. Prepared for City of Vacaville. Woodland, CA.
- Luhdorff and Scalmanini, Consulting Engineers. 2006. City of Vacaville Gibson Canyon Creek Wastewater Treatment Plant, Technical Report, Groundwater Remediation System Performance. Prepared for City of Vacaville. Woodland, CA.
- Luhdorff and Scalmanini, Consulting Engineers. 2007. Evaluation of Hydrogeologic Conditions and Groundwater Supplies for SB 221/610 Requirements. Prepared for City of Vacaville. Woodland, CA.
- Luhdorff and Scalmanini, Consulting Engineers. 2008. Well 16 Aquifer Test, Spring 2007, City of Vacaville, Solano County, CA. Technical Memorandum. May 6, 2008. Woodland, CA.
- Luhdorff and Scalmanini, Consulting Engineers. 2009. Well 16 Water Quality Results from First Year of Operation, Technical Memorandum. April 2, 2009. Woodland, CA.
- Luhdorff and Scalmanini, Consulting Engineers. 2010. *Hydrostratigraphic Interpretation and Groundwater Conditions of the Northern Solano County Deep Aquifer System*. Prepared for the Solano County Water Agency. Woodland, CA.
- Mann, J.F., Jr. 1985. *Groundwater Resources of the Vacaville Area*. Prepared for City of Vacaville.
- Mann, J.F., Jr. 1989. Supplement to Groundwater Resources of the Vacaville Area. Prepared for City of Vacaville.
- McLaughlin, R.J., W.V. Sliter, D.H. Sorg, P.C. Russell, and A.M. Sarna-Wojcicki. 1996. *Large-scale right-slip displacement on the East San Francisco Bay Region fault system: Implications for location of late Miocene to Pliocene Pacific plate boundary.* Tectonics. v. 15, p. 1-18.

- Miller, W.L. 1966. Petrology of the Putah Tuff Member of the Tehama Formation, Yolo and Solano Counties, California. M.S. thesis. University of California, Davis.
- Montgomery Watson Inc. 1993. *Groundwater Management Program: Final Report*. Prepared for City of Vacaville.
- Nolte Associates, Inc., 2001. *City of Vacaville 2000 Urban Water Management Plan*. Prepared for City of Vacaville. Sacramento, CA.
- Nolte Associates, Inc. 2005. *City of Vacaville 2005 Urban Water Management Plan Update*. Prepared for City of Vacaville. Sacramento, CA.
- Prothero, D.R. and E.E. Brabb. 2001. *Magnetic stratigraphy of the lower middle Eocene (type Ulatisian) Vacaville Shale, Solano County, California*. Pacific Section, Society of Economic Paleontologists and Mineralogists. v. 9.
- Siegel, David. 1988. Stratigraphy of the Putnam Peak Basalt and correlation to the Lovejoy Formation, California. M.S. thesis. California State University, Hayward.
- Sims, J.D. and V.A. Frizzell, Jr. 1976. Preliminary photointerpretation map of landslide and other surficial deposits of the Mount Vaca, Vacaville, and parts of Courtland, Davis, Lake Berryessa, and Woodland 15-minute quadrangles, Napa and Solano counties, California. U.S. Geological Survey Miscellaneous Field Studies Map, MF-719, scale 1:62,500.
- Sims, J.D. and T.H. Nilsen. 1972. *Preliminary photointerpretation map of landslide and other surficial deposits of parts of the Pittsburg and Rio Vista 15-minute quadrangles, Contra Costa and Solano counties, California*. U.S. Geological Survey Miscellaneous Field Studies Map MF-322, 2 sheets, scale 1:62,500.
- Sims, J.D. and A.M. Sarna-Wojcicki. 1975. New and revised stratigraphic names in the western Sacramento Valley, California, in Cohee, G.V., and Wright, W.R., Changes in stratigraphic nomenclature by the U.S. Geological Survey, 1973. U.S. Geological Survey Bulletin 1395-A. p. A50-A55.
- Sims, J.D., K.F. Fox, Jr., J.A. Bartow, and E.J. Helley. 1973. *Preliminary geologic map of Solano County and parts of Napa, Contra Costa, Marin, and Yolo Counties, California*. U.S. Geological Survey Miscellaneous Field Studies Map MF-484, 5 sheets, scale 1:62,500.
- Solano Agencies. 2005. Integrated Regional Water Management Plan and Strategic Plan. Elmira, CA.
- Solano County Water Agency. 2005. Proposition 50 Grant Application Solano Integrated Water Management Projects. Elmira, CA.

- Solano Irrigation District and City of Vacaville. 1995. Master Water Agreement. Vacaville, CA.
- Solano Water Authority. In Progress. 2002-2005 Groundwater Report, Groundwater Conditions in Solano County.
- Summers Engineering, Inc. 1988. *Solano Irrigation District Groundwater Resources*. Prepared for SID. Hanford, CA.
- Summers Engineering, Inc. 1995. *North Central Solano County Groundwater Resources Report*. Prepared for Solano Water Authority. Hanford, CA.
- Summers Engineering, Inc. 2006. *SB1938 Groundwater Management Plan Upgrade*. Prepared for Solano Irrigation District. Hanford, CA.
- Summers Engineering, Inc. 2009. 2009 Groundwater Status report Water Levels and Quality. Prepared for Solano Irrigation District. Hanford, CA.
- Theis, C.V. 1935. The relation between the lowering of the piezometric surface and the rate and duration of discharge of a well using groundwater storage. American Geophysical Union Transactions. v. 16, p. 519-524.
- Thomasson, H.G., Jr., F.H. Olmsted, and E.F. LeRoux. 1960. *Geology, water resources and usable ground-water storage capacity of part of Solano County, California*. U.S. Geological Survey Water-Supply Paper 1464.
- Vacaville, City of. In Progess. *General Plan Update Water Supply and Service in Vacaville*, http://www.vacavillegeneralplan.org.
- Walton, W.C. 1985. *Practical Aspects of Groundwater Modeling*. Second Edition. National Water Well Association. Dublin, OH.
- West Yost & Associates. 1995. *City of Vacaville AB 3030 Groundwater Management Plan.* Prepared for City of Vacaville. Davis, CA.
- West Yost & Associates. 2001. City of Vacaville AB 3030 Groundwater Management Plan Update. Prepared for City of Vacaville. Davis, CA.



Table 2-1
City of Vacaville Water Supply<sup>1</sup>

|                            | Surface-                  | Normal               | Year    | Single-Dr            | y Year  | Multiple-E           | ry Year |
|----------------------------|---------------------------|----------------------|---------|----------------------|---------|----------------------|---------|
| Source                     | Water Entitlement (ac-ft) | Percent<br>Available | (ac-ft) | Percent<br>Available | (ac-ft) | Percent<br>Available | (ac-ft) |
| Solano Project             |                           |                      |         |                      |         |                      |         |
| Vacaville Entitlement      | 5,750                     | 99                   | 5,693   | 98                   | 5,635   | 89                   | 5,118   |
| SID Agreement <sup>2</sup> | 2,500                     | 99                   | 2,475   | 98                   | 2,450   | 89                   | 2,225   |
| State Water Project        |                           |                      |         |                      |         |                      |         |
| Vacaville Entitlement      | 6,100                     | 64                   | 3,904   | 63                   | 3,843   | 33                   | 2,013   |
| KCWA Agreement             | 2,878                     | 64                   | 1,842   | 63                   | 1,813   | 33                   | 950     |
| Settlement Water           | 9,320                     | 100                  | 9,320   | 100                  | 9,320   | 100                  | 9,320   |
| Groundwater <sup>3</sup>   |                           | 100                  | 7,000   | 120                  | 8,400   | 110                  | 7,700   |
| Total                      | 26,548                    |                      | 30,233  |                      | 31,461  |                      | 27,325  |

- 1. Source: Memorandum from David B. Okita (General Manager) to City/District Urban Agencies Subject UWMP Reliability Data. August 10, 2010.
- 2. From: City of Vacaville General Plan Update Water Supply and Service in Vacaville (In Process), http://www.vacavillegeneralplan.org.
- 3. Based on: Luhdroff & Scalmanini Consulting Engineers. Sept. 2003, City of Vacaville, SB 610 Water Supply Assessment Groundwater Source Sufficiency.

Table 2-2
City of Vacaville Water Supply Summary (Acre-Feet/Year)

|                     |                               | 200       | 8     | 200       | 9     | 201       | .0           |
|---------------------|-------------------------------|-----------|-------|-----------|-------|-----------|--------------|
| Source Agency       | Description                   | Allocated | Used  | Allocated | Used  | Allocated | Used         |
| Solano Project      | Vacaville Entitlement         | 5750      | 0     | 5750      | 0     | 5750      | 0            |
| Solano Project      | Carryover                     | 5230      | 4553  | 7428      | 2433  | 9793      | 2            |
| Solano Project      | SID Exchange                  | 0         | 0     | 3000      | 3000  | 2500      | 2500         |
| Solano Project      | SID Exchange ( M&I carryover) | 0         | 0     | 678       | 678   | 527       | 527          |
| State Water Project | Table A                       | 3142      | 3142  | 3591      | 2276  | 4489      | <b>3</b> 513 |
| State Water Project | Carryover                     | 1960      | 1960  | 0         | 0     | 1520      | 1520         |
| State Water Project | Benecia Exchange              | 1343      | 1343  | 0         | 0     | 0         | 0            |
| State Water Project | Article 21                    | 0         | 0     | 771       | 771   | 1040      | 1040         |
| State Water Project | Settlement Water (E)          | 682       | 682   | 0         | 0     | 0         | 0            |
| State Water Project | Settlement Water (B)          | 8638      | 1097  | 9320      | 3362  | 9320      | 1481         |
| City of Vacaville   | Groundwater Pumping           |           | 5784  |           | 4647  |           | 5068         |
|                     | Total                         | 26745     | 18561 | 30538     | 17167 | 34652     | 15651        |

Table 2-3
City of Vacaville Water Supply Sources in Normal Year
(acre-feet) 3

| Source                          | 2010   | 2015   | 2020   | 2025   | 2050   |
|---------------------------------|--------|--------|--------|--------|--------|
| Solano Project                  |        |        |        |        |        |
| Vacaville Entitlement           | 5,693  | 5,693  | 5,693  | 5,693  | 5,693  |
| SID Agreement <sup>1</sup>      | 2,475  | 3,094  | 4,084  | 5,569  | 9,850  |
| State Water Project             |        |        |        |        |        |
| Vacaville Entitlement (Table A) | 3,904  | 3,904  | 3,904  | 3,904  | 3,904  |
| KCWA Agreement                  | 1,842  | 1,842  | 1,842  | 1,842  | 1,842  |
| Settlement Water                | 9,320  | 9,320  | 9,320  | 9,320  | 9,320  |
| Groundwater <sup>2</sup>        | 8,000  | 8,000  | 8,000  | 8,000  | 8,000  |
| Total                           | 31,234 | 31,853 | 32,843 | 34,328 | 38,609 |

- 1. From: City of Vacaville General Plan Update Water Supply and Service in Vacaville (In Process), http://www.vacavillegeneralplan.org.
- 2. Based on: Luhdroff & Scalmanini Consulting Engineers. Sept. 2003, *City of Vacaville, SB 610 Water Supply Assessment Groundwater Source Sufficiency.*
- 3. Source: 2010 Draft Urban Water Management Plan. Vander Meadows Draft, W.S.A.R.

Table 2-4
City of Vacaville Annual Well Production (acre-feet)

|              | Е                                | lmira Road                    |                | Nor                               | theast Secto                   | r              |                                  | All Wells                               |                |
|--------------|----------------------------------|-------------------------------|----------------|-----------------------------------|--------------------------------|----------------|----------------------------------|---|----------------|
| Year         | Basal<br>Zone<br>(Wells<br>2-13) | Non-Basal<br>Zone<br>(Well 1) | Total          | Basal<br>Zone<br>(Wells<br>14-16) | Non-Basal<br>Zone<br>(DeMello) | Total          | Basal<br>Zone<br>(Wells<br>2-16) | Non-Basal<br>Zone (Well<br>1 & DeMello) | Total          |
| 1968         |                                  |                               |                |                                   |                                |                |                                  |   | 2862           |
| 1969         |                                  |                               |                |                                   |                                |                |                                  |   | 3046           |
| 1970         |                                  |                               |                |                                   |                                |                |                                  |   | 2871           |
| 1971         |                                  |                               |                |                                   |                                |                |                                  |   | 3198           |
| 1972         |                                  |                               |                |                                   |                                |                |                                  |   | 3255           |
| 1973         |                                  | 110                           | 0.010          |                                   |                                |                |                                  | 110                                     | 3125           |
| 1974         | 2,870                            | 446                           | 3,316          |                                   |                                |                | 2,870                            | 446                                     | 3,316          |
| 1975         | 3,492                            | 478                           | 3,970          |                                   |                                |                | 3,492                            | 478                                     | 3,970          |
| 1976         | 4,525                            | 440                           | 4,965          |                                   |                                |                | 4,525                            | 440                                     | 4,965          |
| 1977         | 4,725                            | 368                           | 5,093          |                                   |                                |                | 4,725                            | 368                                     | 5,093          |
| 1978<br>1979 | 4,667<br>5,858                   | 353<br>327                    | 5,020<br>6,185 |                                   |                                |                | 4,667<br>5,858                   | 353<br>327                              | 5,020<br>6,185 |
| 1979         | 6,595                            | 395                           | 6,990          |                                   |                                |                | 6,595                            | 395                                     | 6,990          |
| 1980         | 7,540                            | 200                           | 7,740          |                                   |                                |                | 7,540                            | 200                                     | 7,740          |
| 1982         | 7,429                            | 254                           | 7,683          |                                   |                                |                | 7,429                            | 254                                     | 7,683          |
| 1983         | 7,751                            | 273                           | 8,024          |                                   |                                |                | 7,751                            | 273                                     | 8,024          |
| 1984         | 6,067                            | 22                            | 6,089          |                                   |                                |                | 6,067                            | 22                                      | 6,089          |
| 1985         | 5,709                            | 144                           | 5,853          |                                   |                                |                | 5,709                            | 144                                     | 5,853          |
| 1986         | 5,595                            | 229                           | 5,824          |                                   |                                |                | 5,595                            | 229                                     | 5,824          |
| 1987         | 6,085                            | 151                           | 6,236          |                                   |                                |                | 6,085                            | 151                                     | 6,236          |
| 1988         | 5,292                            | 129                           | 5,421          |                                   |                                |                | 5,292                            | 129                                     | 5,421          |
| 1989         | 5,897                            | 148                           | 6,045          |                                   |                                |                | 5,897                            | 148                                     | 6,045          |
| 1990         | 5,519                            | 106                           | 5,625          |                                   |                                |                | 5,519                            | 106                                     | 5,625          |
| 1991         | 5,298                            | 149                           | 5,447          |                                   |                                |                | 5,298                            | 149                                     | 5,447          |
| 1992         | 5,405                            | 126                           | 5,531          |                                   |                                |                | 5,405                            | 126                                     | 5,531          |
| 1993         | 4,395                            | 0                             | 4,395          |                                   |                                |                | 4,395                            | 0                                       | 4,395          |
| 1994         | 3,889                            | 4                             | 3,893          |                                   |                                |                | 3,889                            | 4                                       | 3,893          |
| 1995         | 3,856                            | 30                            | 3,886          |                                   |                                |                | 3,856                            | 30                                      | 3,886          |
| 1996         | 3,128                            | 102                           | 3,230          |                                   |                                |                | 3,128                            | 102                                     | 3,230          |
| 1997         | 3,240                            | 14                            | 3,254          | 132                               |                                | 132            | 3,372                            | 14                                      | 3,386          |
| 1998         | 3,369                            | 34                            | 3,403          | 502                               |                                | 502            | 3,871                            | 34                                      | 3,905          |
| 1999         | 3,288                            | 33                            | 3,321          | 775                               |                                | 775            | 4,063                            | 33                                      | 4,096          |
| 2000         | 4,278                            | 52                            | 4,330          | 811                               |                                | 811            | 5,089                            | 52                                      | 5,141          |
| 2001         | 5,162                            | 113                           | 5,275          | 939                               |                                | 939            | 6,101                            | 113                                     | 6,214          |
| 2002         | 5,564                            | 101                           | 5,665          | 973                               | 400                            | 973            | 6,537                            | 101                                     | 6,638          |
| 2003         | 5,456                            | 93                            | 5,549          | 919                               | 160                            | 1,079          | 6,375                            | 253                                     | 6,628          |
| 2004         | 5,130                            | 107                           | 5,237          | 1,325                             | 60                             | 1,385          | 6,455                            | 167                                     | 6,622          |
| 2005         | 4,862                            | 96                            | 4,959          | 1,722                             | 0                              | 1,722          | 6,584                            | 96                                      | 6,680          |
| 2006<br>2007 | 4,840                            | 95<br>101                     | 4,934<br>4,691 | 1,701<br>1,920                    | 0                              | 1,701<br>1,920 | 6,541<br>6,511                   | 1,701<br>101                            | 6,635<br>6,612 |
| 2007         | 4,590<br>3,575                   | 92                            | 3,667          | 2,116                             | 0                              | 2,116          | 5,692                            | 92                                      | 5,784          |
| 2009         | 2,644                            | 54                            | 2,698          | 1,946                             | 0                              | 1,946          | 4,593                            | 54                                      | 4,647          |
| 2010         | 2,902                            | 69                            | 2,090          | 2,097                             | 0                              | 2,097          | 4,999                            | 69                                      | 5,068          |

Table 2-5 Groundwater Quality Northern Solano County

|                    |            |              |               |           |                                 |              | Cat          | ions         |             |                        |       | Anions                               |                                     |             |              |              |             |              |      | Trac    | e Elem | ents   |        |             |                  |          |              |
|--------------------|------------|--------------|---------------|-----------|---------------------------------|--------------|--------------|--------------|-------------|------------------------|-------|--------------------------------------|-------------------------------------|-------------|--------------|--------------|-------------|--------------|------|---------|--------|--------|--------|-------------|------------------|----------|--------------|
| Well Name          | Date       | EC (µmho/cm) | TDS<br>(mg/L) | pН        | Total 1<br>Alkalinity<br>(mg/L) | Ca<br>(mg/L) | Mg<br>(mg/L) | Na<br>(mg/L) | K<br>(mg/L) | SO <sub>4</sub> (mg/L) |       | HCO <sub>3</sub> <sup>1</sup> (mg/L) | NO <sub>3</sub> <sup>1</sup> (mg/L) | F<br>(mg/L) | Al<br>(μg/L) | As<br>(μg/L) | B<br>(mg/L) | Ba<br>(mg/L) |      | Cr (VI) |        |        |        |             | Mn (f)<br>(μg/L) |          | Zn<br>(mg/L) |
|                    |            | 900 b        | 500 b         | 6.5/8.5 b |                                 |              |              |              |             | 250 b                  | 250 b |                                      | 45a                                 | 2 a         | 1000 a       | 10a          | 1 c         | 1 a          | 50 a |         | 1.3a   | 0.30b  | 0.30 b | 50 b        | 50 b             | 50a      | 5a           |
| Well 01            | 2/18/1987  | 780          | 530           | 7.3       | 320                             | 67           | 28           | 56           | 2.9         | 82                     | 3     | 320                                  | 12                                  | -           | -            | <4           | -           | 0.11         | <20  | _       | < 0.02 | < 0.03 | -      | <10         | -                | <2       | < 0.01       |
| Well 01            | 6/19/1990  | 790          | 540           | 7.6       | 310                             | 72           | 25           | 55           | 2.5         | 69                     | 35    | 310                                  | 13                                  | -           | <100         | <10          | -           | < 0.1        | <10  | -       | < 0.05 | < 0.1  | -      | <30         | -                | <5       | < 0.05       |
| Well 01            | 1/1/1994   | -            | 520           | -         | -                               | -            | -            | -            | -           | -                      | 20    | -                                    | 11                                  | -           | -            | 3            | -           | -            | ND   | -       | -      | -      | -      | -           | -                | ND       | -            |
| Well 01            | 1/1/1997   | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | 21    | -                                    | 14.2                                | -           | -            | 4            | -           | -            | ND   | -       | -      | -      | -      | -           | -                | 15       | -            |
| Well 01            | 1/1/1999   | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | 12.8                                | -           | -            | -            | -           | -            | -    | -       | -      | -      | -      | -           | -                | -        | -            |
| Well 01            | 4/29/1999  | 815          | 500           | 7.3       | 326                             | 85.1         | 26.6         | 54.1         | 2.6         | 62                     | 23    | 398                                  | 12.8                                | -           | ND           | 2.6          | -           | ND           | 23   | -       | ND     | ND     | -      | 2.2         | -                | ND       | ND           |
| Well 01            | 10/31/2000 | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | -                                   | -           | -            | -            | -           | -            | ND   | -       | -      | -      | -      | -           | _                | -        | -            |
| Well 01            | 11/1/2000  | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | -                                   | -           | -            | -            | -           | -            | _    | 1.5     | -      | -      | -      | -           | -                | -        | -            |
| Well 01            | 1/1/2001   | -            | _             | _         | _                               | -            | -            | -            | -           | -                      | -     | -                                    | 12.8                                | -           | -            | -            | _           | -            | 2.3  | -       | -      | _      | -      | -           | -                | -        | -            |
| Well 01            | 5/17/2001  | _            | _             | _         | _                               | _            | _            | _            | _           | -                      | _     | _                                    | _                                   | _           | _            | _            | _           | _            | ND   | 1.5     | _      | _      | _      | _           | _                | _        | _            |
| Well 01            | 1/1/2002   | -            | _             | _         | _                               | _            | _            | _            | _           | -                      | _     | _                                    | 12.8                                | _           | -            | _            | _           | _            | _    | _       | _      | _      | _      | _           | _                | _        | -            |
| Well 01            | 3/7/2002   | 789          | 530           | 7.4       | 331                             | 87           | 27           | 59           | 2.8         | 63                     | 23    | 404                                  | 12.76                               | _           | ND           | 2.1          | 0.2         | ND           | ND   | 1.7     | ND     | ND     | _      | ND          | _                | ND       | ND           |
| Well 01            | 5/27/2003  | -            | -             | -         | -                               | -            |              | _            |             | -                      |       | -                                    | 12.4                                | _           |              |              | -           | -            |      | _       | -      | -      | _      | -           | _                | -        |              |
| Well 01            | 3/16/2005  | 656          | 530           | 7.4       | 322                             | 87           | 28           | 57           | 2.9         | 65                     | 24    | _                                    | 12                                  | _           | _            | <2           | _           | _            | <10  | _       | < 0.05 | < 0.1  | _      | <20         | _                | <5       | < 0.05       |
| Well 01            | 1/25/2006  | -            | -             | /         | 322                             | -            | 20           | -            |             | -                      |       | _                                    | 13.3                                | _           | _            | _            | _           | _            | -    | _       | -      | -      | _      | -           | _                | -        |              |
| Well 01            | 3/14/2007  | _            | _             | _         | _                               | _            | _            | _            | _           | _                      | _     | _                                    | 12.4                                | _           |              | _            | _           | _            | _    | _       | _      |        |        | _           | _                | _        |              |
| Well 01            | 1/31/2008  | 846          | 546           | 7.7       | 305                             | 51           | 23           | 47           | 2.7         | 63                     | 23    | -                                    | 12.4                                | -           | ND           | 1.4          | 0.16        | 0.094        | 3.8  | -       | ND     | ND     | -      | ND          | -                | ND       | ND           |
| Well 02            | 2/18/1987  | 520          | 390           | 7.3       | 220                             | 39           | 21           | 44           | 3.6         | 47                     | 16    | 220                                  | 11                                  |             |              | <4           |             | <0.1         | <20  |         | < 0.02 | < 0.03 |        | <10         |                  | <2       | < 0.01       |
| Well 02            | 6/17/1991  | 540          | 310           | 7.8       | 204                             | 39           | 20           | 48           | 2.3         | 36                     | 15    | 204                                  | 7.8                                 | _           | <100         | <10          |             | <0.1         | <10  | _       | < 0.05 | < 0.1  | _      | <30         | _                | <5       | < 0.01       |
| Well 02<br>Well 02 | 1/1/1993   | 540          | 310           | 7.0       | 204                             | 39           | 20           | 40           | 2.3         | 30                     | 13    | 204                                  | 9.3                                 | -           | <100         | ND           | _           | <0.1         | ND   | -       | <0.05  | <0.1   | -      | <b>\</b> 30 | -                | 5        | <0.05        |
| Well 02<br>Well 02 | 3/29/1993  | -            | -             | -         | -                               | -            | -            | -            | -           | _                      | -     | -                                    | 8.4                                 | -           | _            | ND           | -           | -            | ND   | -       | -      | -      | -      | -           | -                | 3        | -            |
| Well 02<br>Well 02 | 6/21/1993  | -            | -             | -         | -                               | -            | -            | -            | -           | 42                     | -     | -                                    | 9.3                                 | -           | -            | -            | -           | -            | -    | -       | -      | -      | -      | -           | -                | -        | -            |
| Well 02<br>Well 02 | 1/1/1994   | -            | -             | -         | -                               | -            | -            | -            | -           | 42                     | -     | -                                    | 5.8                                 | -           | _            | -            | -           | -            | -    | -       | -      | -      | -      | -           | -                | 3        | -            |
| i i                |            |              | 200           | 7.2       | 220                             | -            | 22           |              | 2.5         | 16                     | 16    | 120                                  |                                     | -           |              | -            | -           | 0.1          | -10  | -       | -0.05  | -0.1   | -      | - 20        | -                | -        | -0.05        |
| Well 02            | 5/2/1994   | 570          | 380           | 7.3       | 220                             | 53           | 22           | 51           | 3.5         | 46                     | 16    | 130                                  | 9.5<br>27                           | -           | <50          | <5<br>ND     | -           | 0.1          | <10  | -       | <0.05  | <0.1   | -      | <30         | -                | <5<br>ND | < 0.05       |
| Well 02            | 1/1/1996   |              | 370           | -         | -                               | -            | -            | -            | -           | -                      | 19    | -                                    |                                     | -           | -            | ND           | -           | -            | ND   | -       | -      | -      | -      | -           | -                |          | -            |
| Well 02            | 1/1/1997   | -            | 380           | -         | -                               | -            | -            | -            | -           | -                      | 16    | -                                    | 9.7                                 | -           | -            | ND           | -           | -            | ND   | -       | -      | -      | -      | -           | -                | 9        | -            |
| Well 02            | 1/1/1998   | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | 10.6                                | -           | -            | -            | -           | -            | -    | -       | -      | -      | -      | -           | -                | -        | -            |
| Well 02            | 1/1/1999   | -            | -             | -         | -                               | 40.7         | - 21.2       | -            | -           | 25.2                   | 20.4  | -                                    | 15.1                                | -           | -            | -            | -           | -            | -    | -       | -      | -      | -      | -<br>NTD    | -                | -        | -            |
| Well 02            | 6/3/1999   | 550          | 320           | 7.8       | 243                             | 49.7         | 21.2         | 51.5         | 2           | 35.3                   | 20.4  | 296                                  | 15.1                                | -           | ND           | 1.9          | -           | ND           | 11   | -       | ND     | ND     | -      | ND          | -                | ND       | ND           |
| Well 02            | 10/31/2000 | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | -                                   | -           | -            | -            | -           | -            | 4    | -       | -      | -      | -      | -           | -                | -        | -            |
| Well 02            | 11/1/2000  | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | -                                   | -           | -            | -            | -           | -            | -    | 4.7     | -      | -      | -      | -           | -                | -        | -            |
| Well 02            | 1/1/2001   | -            | 370           | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | 11.1                                | -           | -            | ND           | -           | -            | ND   | 5       | -      | -      | -      | -           | -                | -        | -            |
| Well 02            | 5/17/2001  | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | -                                   | -           | -            | -            | -           | -            | 4.2  | 4.3     | -      | -      | -      | -           | -                | -        | -            |
| Well 02            | 1/1/2002   | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | 11.1                                | -           | -            | -            | -           | -            | -    | -       | -      | -      | -      | -           | -                | -        | -            |
| Well 02            | 3/7/2002   | 558          | 370           | 7.4       | 216                             | 51           | 21           | 44           | 3.3         | 42                     | 16    | 263                                  | 11                                  | -           | ND           | 3            | 0.13        | ND           | 6.2  | 4.7     | ND     | ND     | -      | ND          | -                | ND       | ND           |
| Well 02            | 5/27/2003  | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | 11.1                                | -           | -            | -            | -           | -            | -    | -       | -      | -      | -      | -           | -                | -        | -            |
| Well 02            | 3/16/2005  | 486          | 380           | 7.6       | 223                             | 53           | 22           | 46           | 3.3         | 43                     | 17    | -                                    | 11                                  | -           | -            | 2            | -           | -            | <10  | -       | < 0.05 | < 0.1  | -      | <20         | -                | <5       | < 0.05       |
| Well 02            | 3/15/2006  | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | 13.3                                | -           | -            | -            | -           | -            | -    | -       | -      | -      | -      | -           | -                | -        | -            |
| Well 02            | 5/10/2007  | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | 12                                  | -           | -            | -            | -           | -            | -    | -       | -      | -      | -      | -           | -                | -        | -            |
| Well 02            | 1/31/2008  | 616          | 380           | 8         | 161                             | 85           | 28           | 59           | 2.9         | 40                     | 19    | -                                    | 13.3                                | -           | ND           | 1.6          | 0.24        | 0.067        | 1.7  | -       | 0.0035 | 0.035  | -      | ND          | -                | ND       | ND           |
| Well 03            | 3/30/1987  | 410          | 340           | 7.9       | 210                             | 36           | 20           | 39           | 3.3         | 34                     | 8     | 208                                  | 4                                   | -           | -            | <4           | -           | 0.12         | 20   | -       | < 0.02 | 0.03   | -      | <10         | -                | <3       | < 0.01       |
| Well 03            | 1/1/1992   | -            | -             | -         | -                               | -            | -            | -            | -           | -                      | -     | -                                    | ND                                  | -           | -            | -            | -           | -            | -    | -       | -      | -      | -      | -           | -                | -        | -            |
| Well 03            | 3/3/1992   | 520          | 320           | 7.9       | 200                             | 33           | 24           | 47           | 3           | 45                     | 12    | 200                                  | < 0.4                               | -           | <100         | <10          | -           | 0.14         | 12   | -       | < 0.05 | < 0.1  | -      | <30         | -                | <5       | < 0.05       |

Table 2-5 (continued) Groundwater Quality Northern Solano County

|           |            |       |               |           |                                 |           | Cat          | ions         |             |                        |           | Anions                               |  |          |              |           |          |              |            | Trac    | e Eleme | ents   |        |      |      |          |           |
|-----------|------------|-------|---------------|-----------|---------------------------------|-----------|--------------|--------------|-------------|------------------------|-----------|--------------------------------------|--|----------|--------------|-----------|----------|--------------|------------|---------|---------|--------|--------|------|------|----------|-----------|
| Well Name | Date       | EC    | TDS<br>(mg/L) | pН        | Total 1<br>Alkalinity<br>(mg/L) | Ca (mg/L) | Mg<br>(mg/L) | Na<br>(mg/L) | K<br>(mg/L) | SO <sub>4</sub> (mg/L) | Cl (mg/L) | HCO <sub>3</sub> <sup>1</sup> (mg/L) | NO <sub>3</sub> <sup>1</sup><br>(mg/L) | F (mg/L) | Al<br>(μg/L) | As (ug/L) | B (mg/L) | Ba<br>(mg/L) |            | Cr (VI) |         |        | Fe (f) |      |      |          | Zn (mg/L) |
|           |            | 900 b |               | 6.5/8.5 b | (mg/L)                          | (mg/L)    | (mg/L)       | (mg/L)       | (mg/L)      | 250 b                  | 250 b     | (mg/L)                               | 45a                                    | 2 a      | 1000 a       | 10a       | 1°       | 1a           | 50 a       | (µg/12) |         |        | 0.30 b |      | 50 b | 50a      | 5a        |
| Well 03   | 3/29/1993  | -     | -             | -         | -                               | -         | -            | -            | -           | -                      | -         | -                                    | 5.3                                    | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | -        | -         |
| Well 03   | 6/21/1993  | -     | -             | -         | -                               | -         | -            | -            | -           | 37                     | -         | -                                    | 6.2                                    | -        | -            | ND        | -        | -            | 16         | -       | -       | -      | -      | -    | -    | 6        | _         |
| Well 03   | 1/1/1994   | -     | -             | -         | -                               | -         | -            | -            | -           | -                      | -         | -                                    | 3.5                                    | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | -        | _         |
| Well 03   | 1/26/1995  | 480   | 320           | 7.6       | 200                             | 42        | 21           | 41           | 4           | 38                     | 11        | 120                                  | 6.6                                    | -        | < 50         | 2         | -        | 0.12         | 14         | -       | < 0.05  | < 0.1  | -      | <30  | -    | <5       | < 0.05    |
| Well 03   | 1/1/1996   | -     | 340           | -         | -                               | -         | -            | -            | -           | -                      | 11        | -                                    | -                                      | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | -        | _ !       |
| Well 03   | 3/20/1996  | -     | -             | -         | -                               | -         | -            | -            | -           | -                      | -         | -                                    | 4.9                                    | -        | -            | ND        | -        | -            | ND         | -       | -       | ND     | -      | ND   | -    | -        | _         |
| Well 03   | 1/1/1997   | -     | -             | -         | -                               | -         | _            | _            | -           | -                      | -         | -                                    | 5.8                                    | -        | -            | -         | _        | -            | -          | -       | -       | -      | -      | -    | -    | -        | _         |
| Well 03   | 1/1/1998   | -     | -             | _         | -                               | -         | -            | -            | _           | -                      | -         | -                                    | 5.3                                    | -        | -            | _         | -        | -            | -          | -       | -       | -      | -      | -    | -    | -        | _         |
| Well 03   | 4/29/1999  | 510   | 300           | 7.7       | 218                             | 43.1      | 19.7         | 40.7         | 4.1         | 38                     | 10        | 266                                  | ND                                     | _        | ND           | 3.1       | _        | ND           | 26         | _       | ND      | ND     | _      | ND   | _    | ND       | ND        |
| Well 03   | 8/24/2000  | _     | _             | _         | _                               | _         | _            | _            | _           | _                      | _         | _                                    | _                                      | _        | _            | _         | _        | _            | 14         | 17      | _       | _      | _      | _    | _    | _        | _ !       |
| Well 03   | 10/31/2000 | _     | _             | _         | _                               | _         | _            | _            | _           | _                      | _         | _                                    | _                                      | _        | _            | _         | _        | _            | 12         | -       | _       | _      | _      | _    | _    | _        | _ !       |
| Well 03   | 11/1/2000  | _     | _             | _         | _                               | _         | _            | _            | _           | _                      | _         | _                                    | _                                      | _        | _            | _         | _        | _            |            | 15      | _       | _      | _      | _    | _    | _        | _ !       |
| Well 03   | 1/1/2001   | _     | 330           | _         | _                               | _         | _            | _            | _           | _                      | 9.9       | _                                    | 6.6                                    | _        | _            | _         | _        | _            | _          | -       | _       | _      | _      | _    | _    | _        | _ !       |
| Well 03   | 2/15/2001  |       | 330           | _         | _                               | _         | _            | _            | _           | _                      | 7.7       | _                                    | 0.0                                    | _        |              | _         | _        | _            | 1.1        | _       | _       | _      | _      | _    | _    | _        | _         |
| Well 03   | 5/17/2001  | -     | -             | _         | -                               | _         | -            | -            | -           | _                      | -         | -                                    | -                                      | -        | _            | -         | -        | -            | 1/         | 14.4    | -       | -      | -      | -    | -    | -        | - 1       |
| Well 03   | 3/7/2001   | 506   | 330           | 7.7       | 218                             | 46        | 20           | 40           | 4.3         | 37                     | 9.9       | 266                                  | 6.6                                    | -        | ND           | 2         | ND       | ND           | 15         | 15.9    | ND      | ND     | -      | ND   | -    | ND       | ND        |
| Well 03   | 5/27/2003  | 500   | 330           | 7.7       | 210                             | 40        | 20           | 40           | 4.3         | 31                     | 9.9       | 200                                  | 6.7                                    | -        | ND           | 3         | ND       | ND           | 13         | 13.9    | ND      | ND     | -      | ND   | -    | ND       | ND        |
| Well 03   |            |       | 240           | 7.0       | 210                             | 45        | 20           | 41           | 1.2         | 27                     | -         | -                                    |  | -        | _            | 2.6       | -        | -            | -<br>17    | -       | -0.05   | -0.1   | -      | - 20 | -    | -        | -0.05     |
|           | 3/16/2005  | 461   | 340           | 7.8       | 210                             | 45        | 20           | 41           | 4.2         | 37                     | 9.9       | -                                    | 6.8                                    | -        | -            | 2.6       | -        | -            | 1/         | -       | < 0.05  | < 0.1  | -      | <20  | -    | <5       | < 0.05    |
| Well 03   | 3/15/2006  | -     | -             | -         | -                               | -         | -            | -            | -           | -                      | -         | -                                    | 4.4                                    | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | -        | -         |
| Well 03   | 3/14/2007  | -     | -             | -         | -                               | -         | -            |              | -           | -                      | -         | -                                    | 13.3                                   | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | <u> </u> |           |
| Well 05   | 2/25/1986  | 570   | 380           | 7.3       | 240                             | 54        | 22.6         | 56.8         | -           | 56                     | 24        | 240                                  | 2.7                                    | -        | -            | <4        | -        | < 0.05       | <20        | -       | < 0.02  | < 0.03 | -      | <10  | -    | <5       | < 0.01    |
| Well 05   | 2/22/1989  | 654   | 400           | 7.5       | 230                             | 54        | 22           | 58           | 2.1         | 62                     | 26        | 230                                  | 12                                     | -        | -            | <4        | -        | < 0.06       | 20         | -       | < 0.02  | < 0.03 | -      | <10  | -    | <2       | < 0.02    |
| Well 05   | 3/3/1992   | 700   | 430           | 7.6       | 238                             | 64        | 26           | 47           | 3           | 57                     | 37        | 238                                  | < 0.4                                  | -        | <100         | <10       | -        | < 0.1        | <10        | -       | < 0.05  | < 0.1  | -      | <30  | -    | <5       | < 0.05    |
| Well 05   | 1/1/1993   | -     | -             | -         | -                               | -         | -            | -            | -           | -                      | -         | -                                    | 15.1                                   | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | -        | _ !       |
| Well 05   | 3/29/1993  | -     | -             | -         | -                               | -         | -            | -            | -           | -                      | -         | -                                    | 14.2                                   | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | -        | -         |
| Well 05   | 6/21/1993  | -     | -             | -         | -                               | -         | -            | -            | -           | 56                     | -         | -                                    | 15.1                                   | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | 6        | _         |
| Well 05   | 1/1/1994   | -     | -             | -         | -                               | -         | -            | -            | -           | -                      | -         | -                                    | 12                                     | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | -        | _         |
| Well 05   | 1/26/1995  | 610   | 410           | 7.5       | 240                             | 61        | 25           | 54           | 3           | 52                     | 28        | 140                                  | 13                                     | -        | < 50         | 2         | -        | < 0.1        | <10        | -       | < 0.05  | < 0.1  | -      | <30  | -    | <5       | < 0.05    |
| Well 05   | 1/1/1996   | -     | 460           | -         | -                               | -         | -            | -            | -           | -                      | 30        | -                                    | 13.8                                   | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | -        | _ !       |
| Well 05   | 1/1/1997   | -     | -             | -         | -                               | -         | _            | _            | -           | -                      | -         | -                                    | 13.7                                   | -        | -            | -         | _        | -            | -          | -       | -       | -      | -      | -    | -    | -        | _ !       |
| Well 05   | 1/1/1998   | -     | -             | -         | -                               | -         | -            | -            | -           | -                      | -         | -                                    | 16.8                                   | -        | -            | -         | -        | -            | -          | -       | -       | -      | -      | -    | -    | -        | _ !       |
| Well 05   | 1/1/1999   | -     | _             | _         | -                               | -         | _            | _            | _           | -                      | -         | -                                    | 19.5                                   | _        | j -          | _         | _        | -            | _          | -       | _       | _      | -      | _    | _    | _        | i         |
| Well 05   | 6/3/1999   | 685   | 410           | 7.9       | 248                             | 63.8      | 26.3         | 57.8         | 3.2         | 63                     | 36.9      | 302                                  | 19.7                                   | _        | ND           | 1.6       | _        | ND           | 8.8        | -       | ND      | ND     | -      | ND   | _    | ND       | 0.021     |
| Well 05   | 11/1/2000  | -     | _             | _         | _                               | _         | _            | _            | _           | _                      | _         | _                                    | _                                      | _        | _            | _         | _        | _            | 3.1        | 3.3     | _       | _      | _      | _    | _    | _        | _         |
| Well 05   | 1/1/2001   | _     | 430           | _         | _                               | _         | _            | _            | _           | _                      | 32        | _                                    | 15.9                                   | _        | _            | _         | _        | _            | -          | -       | _       | _      | _      | _    | _    | _        | _ !       |
| Well 05   | 5/17/2001  | _     | _             | _         | _                               | _         | _            | _            | _           | _                      | -         | _                                    | _                                      | _        | i _          | _         | _        | _            | ND         | 3.2     | _       | _      | _      | _    | _    | _        | _         |
| Well 05   | 3/7/2002   | 672   | 430           | 7.5       | 244                             | 62        | 25           | 54           | 2.9         | 60                     | 32        | 297                                  | 15.84                                  | _        | ND           | 2         | 0.27     | ND           | 6.8        | 4.1     | ND      | ND     | _      | ND   | _    | ND       | ND        |
| Well 05   | 5/27/2003  | -     | -             | -         |                                 | _         | -            | _            |             | _                      | -         |                                      | 16.9                                   | _        | - 1.2        | _         | -        | -            | -          | -       | -       | -      | _      |      | _    |          | 1,12      |
| Well 05   | 3/16/2005  | 615   | 440           | 7.6       | 243                             | 65        | 26           | 58           | 3.2         | 64                     | 32        | _                                    | 17                                     | _        | -            | <2        | _        | _            | <10        | _       | < 0.05  | < 0.1  |        | <20  | _    | <5       | < 0.05    |
| Well 05   | 1/25/2006  | -     | 770           | 7.0       | 273                             | 0.5       | -            | 50           | 3.2         | 04                     | 32        | -                                    | 16.8                                   | -        | i -          | ~2        | _        | -            | <b>\10</b> | -       | \U.UJ   | VO.1   | -      | \20  | -    | ~        | \U.U.J    |
| Well 05   | 3/14/2007  | _     | -             | -         |                                 | l -       | -            | -            | -           | 1 -                    | -         | -                                    | 19.9                                   | -        | l -          |           | -        | -            |            | -       | -       | -      |        | -    | -    | -        | -         |
| Well 05   | 1/31/2007  | 774   | 476           | 7.7       | 265                             | 67        | 27           | 58           | 3.2         | 66                     | 33        | -                                    | 18.2                                   | _        | ND           | 1.2       | 0.31     | 0.072        | 2.9        | -       | ND      | ND     | -      | ND   | -    | ND       | ND        |
|           |            |       |               |           |                                 |           |              |              |             |                        |           |                                      |  |          | עאו          |           | 0.51     |              |            |         |         |        |        |      |      |          |           |
| Well 06   | 3/16/1988  | 542   | 340           | 7.7       | 220                             | 44        | 19           | 48           | 4.3         | 36                     | 11        | 220                                  | 7                                      | -        | -            | <4        | -        | < 0.07       | <10        | -       | < 0.02  | < 0.03 | -      | <10  | -    | <2       | < 0.01    |

Table 2-5 (continued) Groundwater Quality Northern Solano County

|                    |                        |           |        |           |                                  |        | Cat    | ions   |        |                 |        | Anions           |                              |        |         |        |        |        |        | Trace   | e Elem | ents   |         |        |        |        |        |
|--------------------|------------------------|-----------|--------|-----------|----------------------------------|--------|--------|--------|--------|-----------------|--------|------------------|------------------------------|--------|---------|--------|--------|--------|--------|---------|--------|--------|---------|--------|--------|--------|--------|
|                    |                        | EC        | TDS    | pН        | Total <sub>1</sub><br>Alkalinity | Ca     | Mg     | Na     | K      | SO <sub>4</sub> | Cl     | HCO <sub>3</sub> | NO <sub>3</sub> <sup>1</sup> | F      | Al      | As     | В      | Ba     | Cr     | Cr (VI) | Cu     | Fe     | Fe (f)  | Mn     | Mn (f) | Se     | Zn     |
| Well Name          | Date                   | (µmho/cm) | (mg/L) |           | (mg/L)                           | (mg/L) | (mg/L) | (mg/L) | (mg/L) | (mg/L)          | (mg/L) | (mg/L)           | (mg/L)                       | (mg/L) | (μg/L)  | (ug/L) | (mg/L) | (mg/L) | (ug/L) | (µg/L)  | (mg/L) | (mg/L) | (mg/L.) | (ug/L) | (ug/L) | (ug/L) | (mg/L) |
|                    |                        | 900 b     | 500 b  | 6.5/8.5 b |                                  | (      | (      | (      | (      | 250b            | 250 b  | (                | 45a                          | 2 a    | 1000 a  | 10a    | 1°     | 1 a    | 50 a   | (F8)    | 1.3a   |        | 0.30 b  |        | 50 b   | 50a    | 5a     |
| Well 06            | 2/6/1991               | 550       | 360    | 7.7       | 226                              | 37     | 21     | 45     | 2.5    | 39              | 13     | 226              | 6.1                          | _      | <100    | <10    | -      | < 0.1  | 11     | -       | < 0.05 | < 0.1  | -       | <30    | _      | <5     | < 0.05 |
| Well 06            | 1/1/1994               | -         | 350    | -         | -                                | -      | -      | -      | -      | -               | 11     | -                | 5.2                          | -      | -       | -      | -      | -      | -      | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 06            | 1/1/1997               | -         | 380    | -         | -                                | -      | -      | -      | -      | -               | 14     | -                | 7.1                          | -      | -       | -      | -      | -      | -      | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 06            | 1/1/1999               | -         | -      | -         | -                                | -      | -      | -      | -      | -               | -      | -                | 10.6                         | -      | -       | -      | -      | -      | -      | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 06            | 4/29/1999              | 610       | 340    | 7.7       | 240                              | 49.9   | 18.9   | 55.8   | 3.3    | 49              | 16     | 292              | 10.6                         | -      | ND      | 1.9    | -      | ND     | 16     | -       | ND     | ND     | -       | 2.6    | -      | ND     | ND     |
| Well 06            | 10/31/2000             | -         | -      | -         | -                                | -      | -      | -      | -      | -               | -      | -                | -                            | -      | -       | -      | -      | -      | 9.3    | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 06            | 11/1/2000              | -         | -      | -         | -                                | -      | -      | -      | -      | -               | -      | -                | -                            | -      | -       | -      | -      | -      | -      | 11      | -      | -      | -       | -      | -      | -      | -      |
| Well 06            | 1/1/2001               | -         | 360    | -         | -                                | -      | -      | -      | -      | -               | 12     | -                | 6.6                          | -      | -       | -      | -      | -      | -      | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 06            | 5/17/2001              | -         | -      | -         | -                                | -      | -      | -      | -      | -               | -      | -                | -                            | -      | -       | -      | -      | -      | ND     | 9.8     | -      | _      | -       | -      | -      | -      | -      |
| Well 06            | 3/7/2002               | 533       | 360    | 7.8       | 222                              | 48     | 19     | 48     | 4.6    | 40              | 12     | 270              | 6.6                          | -      | ND      | 3      | 0.15   | ND     | 12     | 11.2    | ND     | ND     | -       | ND     | -      | ND     | ND     |
| Well 06            | 5/27/2003              | -         | _      | -         | -                                | -      | _      | _      | _      | -               | -      | -                | 6.2                          | _      | -       | _      | _      | _      | _      | _       | _      | _      | _       | -      | _      | _      | -      |
| Well 06            | 3/16/2005              | 465       | 360    | 7.9       | 218                              | 46     | 17     | 55     | 4.3    | 41              | 13     | _                | 6.7                          | _      | _       | 2.4    | _      | _      | 10     | _       | < 0.05 | < 0.1  | _       | <20    | _      | <5     | < 0.05 |
| Well 06            | 1/25/2006              | -         | -      | -         |                                  | _      | -      |        | -      | _               | -      | _                | 7.5                          | _      | _       |        | _      | _      |        | _       | -      | _      | _       | -      | _      | -      | -      |
| Well 06            | 1/31/2008              | 586       | 382    | 8         | 231                              | 48     | 19     | 50     | 4.6    | 43              | 15     | -                | 7.1                          | -      | ND      | 2.1    | 0.16   | 0.067  | 8.9    | -       | ND     | ND     | -       | ND     | -      | ND     | ND     |
| Well 07            | 3/16/1988              | 541       | 350    | 7.8       | 230                              | 40     | 19     | 53     | 5.4    | 32              | 11     | 230              | 4                            | _      | -       | <4     | _      | < 0.08 | <10    | _       | < 0.02 | < 0.03 | _       | <10    | _      | <2     | < 0.01 |
| Well 07            | 6/17/1991              | 640       | 380    | 7.8       | 240                              | 43     | 18     | 66     | 6.3    | 44              | 18     | 240              | 4.3                          | _      | -       | _      | _      | _      | _      | _       | _      | _      | _       | _      | _      | _      | -      |
| Well 07            | 8/2/1994               | -         | -      | -         |                                  | -      | -      | -      | -      | 40              | -      |                  | 4.4                          | _      | -       | 4      | _      | _      | _      | _       | _      | _      | _       | _      | _      | _      | -      |
| Well 07            | 1/1/1996               | _         | 380    | _         | _                                | i .    | _      | _      | _      | _               | 14     | _                | 4                            | _      | i .     | -      | _      | _      | _      | _       | _      | _      | _       | _      | _      | _      | _ i    |
| Well 07            | 1/1/1997               | _         | 350    | _         | _                                | _      | _      | _      | _      | _               | 14     | _                | 4                            | _      | _       | _      | _      | _      | _      | _       | _      | _      | _       | _      | _      | _      | _      |
| Well 07            | 1/1/1998               | i _       | -      | _         | _                                | i _    | _      | _      | _      | i _             | -      | _                | 5.3                          | _      | i _     | _      | _      | _      | _      | _       | _      | _      | _       | _      | _      | _      | _      |
| Well 07            | 1/1/1999               | _         | 360    | _         | _                                |        | _      | _      | _      |                 | _      | _                | 4.4                          | _      |         | _      | _      | _      | _      |         | _      | _      | _       | _      | _      | _      | _      |
| Well 07            | 4/29/1999              | 540       | 360    | 7.8       | 226                              | 41.3   | 16.9   | 52.4   | 5.2    | 42              | 13     | 275              | ND                           | _      | ND      | 3.9    | _      | ND     | 19     | _       | ND     | ND     | _       | ND     | _      | ND     | ND     |
| Well 07            | 10/31/2000             | -         | 500    | 7.0       | -                                | 41.5   | 10.9   | 32.4   | 3.2    | 42              | -      | -                | ND                           | _      | ND      | 3.9    | - [    | ND     | 8.1    | - [     | ND     | ND     | _       | ND     | _      | ND     | ND     |
| Well 07            | 11/1/2000              | _         | _      | _         | _                                | i -    | _      | _      | _      | i -             | _      | _                | _                            | _      | i -     | _      | _      |        | 0.1    | 9.9     | _      | _      | _       | _      | _      | _      | - 1    |
| Well 07            | 1/1/2000               | _         | 360    | -         | -                                | _      | -      | -      | -      | _               | 12     | -                | 4.4                          | -      | _       | -      | -      | -      | -      | 9.9     | -      | -      | -       | -      | -      | -      | -      |
| Well 07            | 5/17/2001              | _         | 300    | -         | -                                | ·      | _      | _      | _      | i -             | 12     | -                | 4.4                          | -      | · -     | -      | -      | -      | ND     | 8.5     | -      | -      | -       | -      | -      | -      | -      |
| Well 07            | 3/14/2001              | 521       | 360    | 8         | 228                              | 41     | 17     | 57     | 5.8    | 41              | 12     | 277              | 4.224                        | -      | ND      | 4.1    | 0.17   | ND     | 8.3    | 9.5     | ND     | ND     | -       | ND     | -      | ND     | ND     |
|                    | i                      | i         | 300    | 0         | 220                              | 41     | 17     | 31     | 3.6    | 41              | 12     | 211              | 4.224                        | -      | ND      | 4.1    | 0.17   | ND     | 6.3    | 9.3     | ND     | ND     | -       | ND     | -      | ND     | ND     |
| Well 07<br>Well 07 | 5/27/2003              | 458       | 260    | 7.0       | 218                              | - 12   | 18     | 56     | 5.6    | 41              | 13     | -                | 4.3                          | -      | -       | 3.5    | -      | -      | 11     | -       | -0.05  | < 0.1  | -       | <20    | -      | -      | < 0.05 |
|                    | 3/16/2005              | 436       | 360    | 7.8       | 210                              | 42     | 16     | 30     | 3.0    | 41              | 13     | -                |                              | -      | l -     | 3.3    | -      | -      | 11     | -       | < 0.05 | <0.1   | -       | <20    | -      | <5     | <0.03  |
| Well 07            | 1/25/2006              | -         | -      | -         | -                                | -      | -      | -      | -      | -               | -      | -                | 5.3                          | -      | -       | -      | -      | -      | -      | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 07<br>Well 07 | 3/14/2007<br>1/31/2008 | 580       | 384    | 7.9       | 228                              | 43     | 18     | 59     | 6.1    | 43              | 14     | -                | 4.9<br>4.4                   | -      | -<br>ND | 3.1    | 0.19   | 0.082  | 8      | -       | ND     | ND     | -       | ND     | -      | ND     | ND     |
| Well 08            | 3/16/1988              | 588       | 360    | 7.7       | 220                              | 47     | 23     | 47     | 3      | 43              | 16     | 220              | 13                           |        | ND      | <4     | 0.17   | <0.08  | <10    |         | <0.03  | <0.03  |         | <10    |        | <2     | <0.04  |
|                    |                        | 530       |        |           | -                                | 42     | 18     |        | 5      |                 |        | 223              |                              | -      | <100    |        | -      |        |        | -       |        |        | -       | <30    | -      |        | < 0.04 |
| Well 08            | 2/6/1991               |           | 360    | 7.5       | 223                              | 42     | 18     | 48     | 3      | 37              | 10     | 223              | 5.6                          | -      | <100    | <10    | -      | < 0.1  | <10    | -       | < 0.05 | < 0.1  | -       | <.30   | -      | <5     | <0.05  |
| Well 08            | 1/1/1993               | -         | -      | -         | -                                | -      | -      | -      | -      | _               | -      | -                | 3.8                          | -      | -       | -      | -      | -      | -      | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 08            | 3/29/1993              | -         | -      | -         | -                                | l -    | -      | -      | -      | 27              | -      | -                | 13.7                         | -      | -       | -      | -      | -      | - 15   | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 08            | 6/21/1993              | -         | -      | -         | -                                | -      | -      | -      | -      | 37              | -      | -                | 4                            | -      | -       | -      | -      | -      | 15     | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 08            | 1/1/1994               | -         | 430    | -         | -                                | -      | -      | -      | -      |                 | -      | 150              | 6.4                          | -      | 50      | -      | -      | - 0.12 | - 40   | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 08            | 5/2/1994               | 630       | 430    | 7.5       | 240                              | 59     | -      | 63     | 4.7    | 45              | 17     | 150              | 10                           | -      | <50     | <5     | -      | 0.12   | <10    | -       | < 0.05 | < 0.1  | -       | <30    | -      | <5     | < 0.05 |
| Well 08            | 1/1/1996               | -         | 400    | -         | -                                | -      | -      | -      | -      | -               | 17     | -                | 9.8                          | -      | -       | -      | -      | -      | -      | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 08            | 1/1/1997               | -         | -      | -         | -                                | -      | -      | -      | -      | -               | 11     | -                | 4                            | -      | -       | -      | -      | -      | -      | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 08            | 1/1/1998               | -         | -      | -         | -                                | -      | -      | -      | -      | -               | -      | -                | 10.2                         | -      | -       | -      | -      | -      | -      | -       | -      | -      | -       | -      | -      | -      | -      |
| Well 08            | 1/1/1999               | -         | -      | -         | -                                | l -    | -      | -      | -      | -               | -      | -                | 5.3                          | -      | -       | -      | -      | -      | -      | -       | -      | -      | -       | -      | -      | -      | -      |

Table 2-5 (continued) Groundwater Quality Northern Solano County

|           |            |           |        |           |                                  |        | Cat    | ions   |           |        |        | Anions                        |                              |        |        |        |        |        |        | Trac    | e Elem | ents   |        |        |        |        |        |
|-----------|------------|-----------|--------|-----------|----------------------------------|--------|--------|--------|-----------|--------|--------|-------------------------------|------------------------------|--------|--------|--------|--------|--------|--------|---------|--------|--------|--------|--------|--------|--------|--------|
|           |            | EC        | TDS    | pН        | Total <sub>1</sub><br>Alkalinity | Ca     | Mg     | Na     | K         | $SO_4$ | Cl     | HCO <sub>3</sub> <sup>1</sup> | NO <sub>3</sub> <sup>1</sup> | F      | Al     | As     | В      | Ba     | Cr     | Cr (VI) | Cu     | Fe     | Fe (f) | Mn     | Mn (f) | Se     | Zn     |
| Well Name | Date       | (µmho/cm) | (mg/L) |           | (mg/L)                           | (mg/L) | (mg/L) | (mg/L) | (mg/L)    | (mg/L) | (mg/L) | (mg/L)                        | (mg/L)                       | (mg/L) | (μg/L) | (ug/L) | (mg/L) | (mg/L) | (ug/L) | (µg/L)  | (mg/L) | (mg/L) | (mg/L) | (ug/L) | (ug/L) | (ug/L) | (mg/L) |
|           |            | 900 в     | 500 b  | 6.5/8.5 b |                                  | (      | (      | (      | (         | 250 b  | 250 b  | ( <b>g</b> )                  | 45a                          | 2 a    | 1000 a | 10a    | 1°     | 1 a    | 50 a   | (FS)    | 1.3a   |        | 0.30 b |        | 50 b   | 50a    | 5a     |
| Well 08   | 10/28/1999 | 550       | 340    | 7.5       | 222                              | 41.3   | 17.7   | 49.5   | 4.9       | 37.9   | 12.1   | 271                           | ND                           | -      | ND     | 4.2    | -      | ND     | 30     | -       | 0.005  | ND     | -      | ND     | -      | ND     | ND     |
| Well 08   | 8/24/2000  | -         | -      | -         | -                                | -      | -      | -      | -         | -      | -      | -                             | -                            | -      | -      | -      | -      | -      | 7      | 9       | -      | -      | -      | -      | -      | -      | -      |
| Well 08   | 10/31/2000 | -         | -      | -         | -                                | -      | -      | -      | -         | -      | -      | -                             | -                            | -      | -      | -      | -      | -      | 10     | -       | -      | -      | -      | -      | -      | -      | -      |
| Well 08   | 11/1/2000  | -         | -      | -         | -                                | -      | -      | -      | -         | -      | -      | -                             | -                            | -      | -      | -      | -      | -      | -      | 12      | -      | -      | -      | -      | -      | -      | -      |
| Well 08   | 1/1/2001   | -         | 350    | -         | -                                | -      | -      | -      | -         | -      | 11     | -                             | 4.4                          | -      | -      | -      | -      | -      | -      | -       | -      | -      | -      | -      | -      | -      | -      |
| Well 08   | 2/8/2001   | -         | -      | -         | -                                | -      | -      | -      | -         | -      | -      | -                             | -                            | -      | -      | -      | -      | -      | 6.6    | -       | -      | -      | -      | -      | -      | -      | -      |
| Well 08   | 2/15/2001  | -         | -      | -         | -                                | -      | -      | -      | -         | -      | -      | -                             | -                            | -      | -      | -      | -      | -      | ND     | -       | -      | -      | -      | -      | -      | -      | -      |
| Well 08   | 5/17/2001  | -         | -      | -         | -                                | -      | -      | -      | -         | -      | -      | -                             | -                            | -      | -      | -      | -      | -      | ND     | 6.4     | -      | -      | -      | -      | -      | -      | -      |
| Well 08   | 3/14/2002  | 504       | 350    | 7.7       | 222                              | 43     | 18     | 52     | 5.7       | 37     | 11     | 270                           | 4.4                          | -      | 170    | 5.4    | 0.16   | 0.1    | 17     | 12.8    | ND     | -      | -      | ND     | -      | ND     | ND     |
| Well 08   | 5/27/2002  | -         | -      | -         | -                                | -      | -      | -      | -         | -      | -      | -                             | -                            | -      | -      | -      | -      | -      | -      | -       | -      | ND     | -      | -      | -      | -      | -      |
| Well 08   | 3/16/2005  | 451       | 360    | 7.7       | 215                              | 41     | 18     | 49     | 5.5       | 37     | 10     | -                             | 4                            | -      | -      | 3.8    | -      | -      | 13     | -       | < 0.05 | < 0.1  | -      | < 20   | -      | <5     | < 0.05 |
| Well 08   | 1/25/2006  | -         | -      | -         | _                                | -      | _      | -      | -         | -      | -      | -                             | 8.9                          | -      | -      | _      | -      | _      | -      | _       | -      | _      | -      | -      | -      | -      | -      |
| Well 08   | 3/14/2007  | -         | -      | -         | _                                | -      | _      | -      | -         | -      | -      | -                             | 4.9                          | -      | -      | _      | -      | _      | -      | _       | -      | _      | -      | -      | -      | -      | -      |
| Well 08   | 1/31/2008  | 552       | 270    | 8         | 222                              | 42     | 19     | 50     | 5.8       | 38     | 11     | -                             | 4.1                          | -      | ND     | 3      | 0.17   | 0.088  | 11     | -       | ND     | ND     | -      | ND     | -      | ND     | ND     |
| Well 09   | 1/30/1989  | 524       | 300    | 7.8       | 210                              | 39     | 21     | 45     | 4.2       | 37     | 17     | 210                           | 4                            | -      | -      | <4     | -      | 0.11   | 20     | -       | < 0.02 | 0.12   | -      | <30    | -      | <1     | 0.07   |
| Well 09   | 3/2/1992   | 690       | 480    | 7.2       | 240                              | 60     | 28     | 57     | <3        | 96     | 17     | 240                           | < 0.4                        | -      | <100   | <10    | -      | < 0.1  | <10    | _       | < 0.05 | < 0.1  | -      | < 30   | -      | <5     | < 0.05 |
| Well 09   | 3/3/1992   | -         | -      | -         | _                                | -      | _      | -      | -         | -      | -      | -                             | -                            | -      | -      | ND     | -      | _      | ND     | _       | -      | _      | -      | -      | -      | -      | -      |
| Well 09   | 3/29/1993  | _         | _      | _         | _                                | -      | _      | _      | _         | -      | _      | _                             | 8                            | _      | _      | _      | _      | _      | _      | _       | _      | _      | _      | _      | _      | _      | - 1    |
| Well 09   | 6/21/1993  | -         | _      | _         | _                                | -      | _      | _      | _         | 33     | _      | -                             | 4                            | _      | -      | ND     | _      | 0.1    | ND     | _       | _      | _      | -      | _      | -      | 3      | -      |
| Well 09   | 1/1/1994   | _         | _      | _         | _                                | _      | _      | _      | _         | _      | _      | _                             | 7.5                          | _      | _      | _      | _      | _      | _      | _       | _      | _      | _      | _      | _      | _      | _      |
| Well 09   | 1/26/1995  | 490       | 330    | 7.6       | 200                              | 39     | 23     | 45     | 3         | 43     | 11     | 120                           | 4.9                          | _      | < 50   | 2      | _      | 0.11   | 15     | _       | < 0.05 | < 0.1  | _      | < 30   | _      | <5     | < 0.05 |
| Well 09   | 1/1/1996   | _         | 340    | _         |                                  | _      | _      | _      | _         | _      | 10     | _                             | 4                            | _      | _      | _      | _      | _      | _      | _       | _      | _      | _      | _      | _      | _      | _      |
| Well 09   | 3/20/1996  | _         | -      | _         | _                                | _      | _      | _      | _         | _      | -      | _                             | 4                            | _      | -      | ND     | _      | _      | ND     | _       | _      | ND     | _      | ND     | _      | _      | _      |
| Well 09   | 1/1/1997   | _         | _      | _         | _                                | _      | _      | _      | _         | _      | _      | _                             | 7.1                          | _      | _      | _      | _      | _      | _      | _       | _      | _      | _      | _      | _      | _      | _      |
| Well 09   | 1/1/1998   | _         | _      | _         | _                                | _      | _      | _      | _         | _      | _      | _                             | 5.3                          | _      | -      | _      | _      | _      | _      | _       | _      | _      | _      | _      | _      | _      | _      |
| Well 09   | 1/1/1999   | _         | _      | _         | _                                | _      | _      | _      | _         | _      | _      | _                             | 5.3                          | _      | i _    | _      | _      | _      | _      | _       | _      | _      | _      | _      | _      | _      | _      |
| Well 09   | 4/29/1999  | _         | _      | _         | _                                | _      | _      | _      | _         | _      | _      | _                             | 5.3                          | _      | _      | 3      | _      | _      | 30     | _       | _      | ND     | _      | ND     | _      | _      | _      |
| Well 09   | 10/28/1999 | 515       | 320    | 7.6       | 206                              | 37.4   | 20.6   | 45.1   | 3.2       | 44.1   | 11.3   | 251                           | ND                           | _      | ND     | 3.1    | _      | ND     | 30     | _       | ND     | ND     | _      | ND     | _      | ND     | ND     |
|           | 8/24/2000  | -         | -      | -         | -                                | -      | -      | -      | -         | -      | -      | -                             | -                            | _      | -      | -      | _      | -      | 18     | 23      | _      | -      | _      | _      | _      | _      | -      |
| Well 09   | 10/31/2000 | _         | _      | _         | _                                | _      | _      | _      | _         | _      | _      | _                             | _                            | _      | _      | _      | _      | _      | 15     | _       | _      | _      | _      | _      | _      | _      | _      |
| Well 09   | 11/1/2000  | _         | _      | _         | _                                | _      | _      | _      | _         | _      | _      | _                             | _                            | _      | -      | _      | _      | _      | -      | 17      | _      | _      | _      | _      | _      | _      | _      |
| Well 09   | 1/1/2001   | _         | 300    | _         | _                                | _      | _      | _      | _         | _      | 8.6    | _                             | 4 1                          | _      | i _    | _      | _      | _      | _      | -       | _      | _      | _      | _      | _      | _      | _      |
| Well 09   | 2/15/2001  | _         | -      | _         | _                                | _      | _      | _      | _         | _      | -      | _                             | -                            | _      | _      | _      | _      | _      | 18     | _       | _      | _      | _      | _      | _      | _      | _      |
| Well 09   | 5/17/2001  | _         | _      | _         | _                                | _      | _      | _      | _         | _      | _      | _                             | _                            | _      | i _    | _      | _      | _      | 16     | 17.9    | _      | _      | _      | _      | _      | _      | _      |
| Well 09   | 3/14/2002  | 454       | 300    | 7.8       | 209                              | 36     | 20     | 41     | 4.1       | 31     | 8.6    | 255                           | 4.048                        | _      | ND     | 44     | 0.13   | 0.11   | 22     | 20.4    | ND     | ND     | _      | ND     | _      | ND     | ND     |
| Well 09   | 5/27/2003  | -         | -      | -         |                                  | _      | _      | -      | -         | _      | -      |                               | 4                            | _      |        | -      | -      | -      | -      |         | -      | -      | _      | -      | _      | -      |        |
| Well 09   | 3/16/2005  | 429       | 300    | 7.8       | 200                              | 36     | 20     | 42     | 4.2       | 32     | 8.5    | _                             | 3.9                          | _      | _      | 3.3    | _      | _      | 19     | _       | < 0.05 | < 0.1  | _      | <20    | _      | <5     | < 0.05 |
| Well 09   | 1/25/2006  | -         | -      | -         | -                                | -      | -      | -12    |           | -      | -      | _                             | 10.2                         | _      | _      | -      |        |        | -      | _       | -0.03  |        | _      | -      |        | _      | .0.03  |
|           | 5/10/2007  | -         | -      |           | -                                | _      | -      | -      | -         | _      | -      | -                             | 16.4                         | -      | _      | -      | _      | _      | _      | -       | _      | _      | -      | -      | -      | _      | -      |
| Well 13   | 6/7/1990   | 530       | 340    | 7.9       | 230                              | 44     | 21     | 43     | 2.6       | 40     | 16     | 230                           | 7.7                          |        | 50     | <5     | 0.1    | <0.1   | <10    |         | < 0.05 | <0.1   |        | <30    |        | <5     | < 0.05 |
| Well 13   | 9/30/1991  | 540       |        | 7.74      | 210                              | 2.5    | 2.06   | 2      | 2.0<br><3 | _      | 18     | 210                           |                              | -      | 30     | <3     | 0.1    | <0.1   | <10    | -       | <0.03  | <0.1   | -      | <30    | -      | <>>    | <0.03  |
|           |            |           | 370    | 1.74      | ∠10                              | 2.3    | ∠.06   | 2      | <>3       | 41     |        | ∠10                           | 6.6                          | -      | _      | -      | -      | -      | -      | -       | -      | -      | -      | -      | -      | -      | -      |
| Well 13   | 1/1/1992   | -         | 480    | -         | -                                | -      | -      | -      | -         | -      | 12     | -                             | ND                           | -      | _      | -      | -      | -      | -      | -       | -      | -      | -      | -      | -      | -      | -      |
| Well 13   | 1/1/1994   | -         | 330    | -         | -                                | -      | -      | -      | -         | -      | 13     | -                             | 6                            | -      | I -    | -      | -      | -      | -      | -       | -      | -      | -      | -      | -      | -      | -      |

Table 2-5 (continued) Groundwater Quality Northern Solano County

|                    |                      |           |        |           |                                  |       | Cat    | ions   |        |                 |        | Anions           |                              |        |        |        |         |        |        | Trac    | e Eleme | ents    |         |                   |        |         |         |
|--------------------|----------------------|-----------|--------|-----------|----------------------------------|-------|--------|--------|--------|-----------------|--------|------------------|------------------------------|--------|--------|--------|---------|--------|--------|---------|---------|---------|---------|-------------------|--------|---------|---------|
|                    |                      | EC        | TDS    | pН        | Total <sub>1</sub><br>Alkalinity | Ca    | Mg     | Na     | K      | SO <sub>4</sub> | Cl     | HCO <sub>3</sub> | NO <sub>3</sub> <sup>1</sup> | F      | Al     | As     | В       | Ba     | Cr     | Cr (VI) | Cu      | Fe      | Fe (f)  | Mn                | Mn (f) | Se      | Zn      |
| Well Name          | Date                 | (µmho/cm) | (mg/L) | •         | (mg/L)                           |       | _      | (mg/L) | (mg/L) | (mg/L)          | (mg/L) | (mg/L)           | (mg/L)                       | (mg/L) | (μg/L) | (ng/L) | (mg/L.) | (mg/L) | (ng/L) | (μg/L)  | (mg/L)  | (mg/L.) | (mg/L.) | (110/L)           | (nø/L) | (110/L) | (mg/L)  |
|                    |                      | 900 b     |        | 6.5/8.5 b | ( <b>g</b> , 2)                  | (g/2) | (mg/2) | (mg/2) | (g/ 2) | 250 b           | 250 b  | (g/ 2.)          | 45a                          | 2 a    | 1000 a | 10a    | 1°      | 1a     | 50 a   | (FS/2)  |         | 0.30b   |         |                   | 50 b   | 50a     | 5a      |
| Well 13            | 1/1/1997             | -         | 330    | -         | -                                | -     | -      | -      | -      | -               | 20     | -                | 8                            | -      | -      | -      | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 13            | 1/1/1999             | -         | 310    | -         | -                                | -     | -      | -      | -      | -               | -      | -                | 8.4                          | -      | -      | -      | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 13            | 4/29/1999            | 490       | 310    | 8.1       | 172                              | 45.6  | 8.42   | 46.1   | 3.1    | 43              | 18     | 209              | ND                           | -      | ND     | 1.9    | -       | ND     | 16     | -       | 0.028   | ND      | -       | ND                | -      | ND      | ND      |
| Well 13            | 10/31/2000           | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | -                            | -      | -      | -      | -       | -      | 6.4    | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 13            | 11/1/2000            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | -                            | -      | -      | -      | -       | -      | -      | 6.8     | -       | -       | -       | -                 | -      | -       | -       |
| Well 13            | 1/1/2001             | -         | 360    | -         | -                                | -     | -      | -      | -      | -               | 19     | -                | 11.1                         | -      | -      | -      | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 13            | 5/17/2001            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | -                            | -      | -      | -      | -       | -      | ND     | 7.8     | -       | -       | -       | -                 | -      | -       | -       |
| Well 13            | 3/7/2002             | 553       | 360    | 7.7       | 219                              | 47    | 23     | 46     | 2.8    | 43              | 19     | 267              | 11                           | -      | ND     | 2      | 0.15    | ND     | ND     | 7.8     | ND      | ND      | -       | ND                | -      | ND      | ND      |
| Well 13            | 5/27/2003            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | 11.1                         | -      | -      | -      | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 13            | 3/16/2005            | 511       | 350    | 7.8       | 208                              | 45    | 24     | 48     | 2.8    | 47              | 21     | -                | 12                           | -      | -      | 2      | -       | -      | <10    | -       | < 0.05  | < 0.1   | -       | <20               | -      | <5      | < 0.05  |
| Well 13            | 1/25/2006            | -         | _      | _         | -                                | -     | _      | _      | _      | -               | -      | -                | 11.5                         | _      | -      | _      | _       | _      | _      | _       | -       | _       | -       | _                 | -      | _       | -       |
| Well 13            | 3/14/2007            | -         | _      | _         | _                                | _     | _      | _      | _      | _               | _      | _                | 5.3                          | _      | _      | _      | _       | _      | _      | _       | _       | _       | _       | _                 | _      | _       | _       |
| Well 13            | 1/31/2008            | 615       | 372    | 7.9       | 229                              | 49    | 25     | 47     | 3.1    | 45              | 21     | -                | 12                           | -      | ND     | 1.6    | 0.18    | 0.083  | 8.2    | _       | ND      | ND      | -       | ND                | _      | ND      | ND      |
| Well 14            | 10/20/1993           | 452       | 290    | 8         | _                                | 16    | 10     | 58     | 3.1    | 23              | < 0.5  | 230              | 3.1                          |        | <50    | 4.1    |         | 0.14   | 13     |         | < 0.02  | 0.075   |         | <5                |        | <1      | < 0.005 |
| Well 14            | 1/1/1997             | 432       | 290    | o         | -                                | 10    | 10     | 36     | 3.1    | 23              | <0.5   | 230              | 2.2                          | -      | <50    | 4.1    | -       | 0.14   | 13     | -       | <0.02   | 0.073   | -       | $\langle \rangle$ | -      | <1      | <0.003  |
| Well 14            | 8/4/1997             |           |        | 0.2       | 190                              | 17    | 12     | 74     | 4      | 20              | 10     | 190              | 2.2                          | -      | ND     | 7      | -       | 0.11   | 10     | -       | ND      | 0.11    | -       | ND                | -      | NID.    | ND      |
| Well 14<br>Well 14 | 8/4/1997<br>1/1/1998 | 460       | 280    | 8.2       | 190                              | 17    | 12     | /4     | 4      | 30              | 10     | 190              | ND                           | -      | ND     | /      | -       | 0.11   | 10     | -       | ND      | 0.11    | -       | ND                | -      | ND      | ND      |
|                    |                      |           | 200    | 7.0       | 100                              | 10    | 10     | 70     | -      | 25              | 9      | 220              |                              | -      | ND.    | -      | -       | 0.1    | 20     | -       | NID.    | NID     | -       | NID               | -      | NID.    | - ND    |
| Well 14            | 6/4/1998             | 450       | 290    | 7.9       | 190                              | 18    | 12     | 70     | 4      | 25              | -      | 230<br>230       | 2                            | -      | ND     | 5      | -       | 0.1    | 20     | -       | ND      | ND      | -       | ND                | -      | ND      | ND      |
| Well 14            | 8/28/1998            | 440       | 330    | 7.9       | 190                              | 18    | 13     | 59     | 3      | 29              | 10     | 230              | -                            | -      | ND     | 3      | -       | 0.1    | 20     | -       | ND      | ND      | -       | ND                | -      | ND      | ND      |
| Well 14            | 8/31/1998            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | ND                           | -      | -      | -      | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 1/1/1999             | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | 3.1                          | -      | -      |        | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 4/29/1999            | 440       | 280    | 8.1       | 197                              | 20.6  | 13.7   | 60.2   | 3.1    | 26              | 8.3    | 240              | ND                           | -      | ND     | 5.4    | -       | 0.13   | 28     | -       | 0.0029  | ND      | -       | ND                | -      | ND      | ND      |
| Well 14            | 1/1/2000             | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | 3                            | -      | -      | -      | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 8/24/2000            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | -                            | -      | -      | -      | -       | -      | 21     | 23      | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 10/31/2000           | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | -                            | -      | -      | -      | -       | -      | 17     | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 11/1/2000            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | -                            | -      | -      | -      | -       | -      | -      | 19      | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 1/1/2001             | -         | 290    | -         | -                                | -     | -      | -      | -      | -               | 8.8    | -                | 3.1                          | -      | -      | -      | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 2/15/2001            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | -                            | -      | -      | -      | -       | -      | 21     | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 5/17/2001            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | -                            | -      | -      | -      | -       | -      | 19     | 20.3    | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 3/14/2002            | 441       | 290    | 8.1       | 199                              | 21    | 14     | 62     | 3.4    | 25              | 8.8    | 242              | 3                            | -      | ND     | 6.2    | 0.15    | 0.12   | 18     | 22.2    | ND      | ND      | -       | ND                | -      | ND      | ND      |
| Well 14            | 5/27/2003            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | ND                           | -      | -      | -      | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 3/16/2005            | 393       | 280    | 8.1       | 193                              | 21    | 14     | 61     | 3.3    | 26              | 7.8    | -                | 2.9                          | -      | -      | 4.8    | -       | -      | 20     | -       | < 0.05  | < 0.1   | -       | <20               | -      | <5      | < 0.05  |
| Well 14            | 1/25/2006            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | 3.1                          | -      | -      | -      | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 5/10/2007            | -         | -      | -         | -                                | -     | -      | -      | -      | -               | -      | -                | 3.1                          | -      | -      | -      | -       | -      | -      | -       | -       | -       | -       | -                 | -      | -       | -       |
| Well 14            | 1/31/2008            | 471       | 288    | 8.2       | 199                              | 22    | 14     | 62     | 3.5    | 27              | 8.1    | -                | 3                            | -      | ND     | 3.9    | 0.17    | 0.12   | 17     | -       | ND      | ND      | -       | ND                | -      | ND      | 0.065   |
| MW-14              | 3/25/1993            | 453       | 290    | 8.1       | 190                              | 17    | 12     | 66     | 3.5    | 29              | 10     | 240              | 2.2                          | -      | 740    | <10    | -       | 0.11   | <10    | -       | < 0.05  | 1.3     | < 0.03  | 64                | <10    | 1.4     | < 0.05  |
| Well 15            | 2/22/2001            | 440       | 300    | 8.1       | 210                              | 20    | 12     | 73     | 3.8    | 23              | 8.9    | _                | 2.5                          | _      | -      | 3.9    | 0.22    | _      | 20     | 12      | < 0.05  | < 0.1   | _       | <10               | _      | <5      | < 0.05  |
| Well 15            | 3/16/2005            | 395       | 300    | 8         | 198                              | 26    | 14     | 55     | 5.1    | 21              | 7.9    | _                | 3.5                          | _      | _      | 3.8    | _       | _      | 13     | _       | < 0.05  | <0.1    | _       | <20               | _      | <5      | < 0.05  |
| Well 15            | 1/25/2006            | -         | -      | -         | -                                |       | -      | -      | -      | _               | -      | _                | 3.1                          | _      | _      | -      | _       | _      | -      | _       | -       | -       | _       | -                 | _      | -       | -       |
| Well 15            | 5/10/2007            | _         | _      | _         | _                                | _     | _      | _      | _      | _               | _      | _                | 2.7                          | _      | i -    | _      | _       | _      | _      | _       | _       | _       | _       | _                 | _      | _       | _ i     |
| Well 15            | 1/31/2008            | 483       | 298    | 8.1       | 197                              | 21    | 12     | 70     | 4.2    | 24              | 8.2    | -                | 3.1                          | -      | ND     | 3.5    | 0.22    | 0.11   | 11     | -       | ND      | ND      | -       | ND                | -      | ND      | ND      |
| MW-15-1815ft       | 1/6/1999             | 458       | 277    | 7.91      | -                                | 23.1  | 9.91   | 53.6   | 4.17   | 16.7            | 10.8   | 210              | 3.73                         | -      | <50    | <2     | 0.109   | 0.0691 | <5     | -       | < 0.005 | 2.2     | 0.261   | 27.4              | 28.9   | <4      | -       |

Table 2-5 (continued) Groundwater Quality Northern Solano County

| Well Name Date  | Ca<br>(mg/L) | Mg<br>(mg/L) | Na     | K    | SO <sub>4</sub> | CII. | 1                       | 1                                |                    |                        |                                 |          |              |      |                   |         |       |       |      |      |     |                    |
|---|--------------|--------------|--------|------|-----------------|------|-------------------------|----------------------------------|--------------------|------------------------|---------------------------------|----------|--------------|------|-------------------|---------|-------|-------|------|------|-----|--------------------|
|   |              | (IIIg/L)     | (mg/L) |      | -               |      | HCO <sub>3</sub> (mg/L) | NO <sub>3</sub><br>(mg/L)<br>45a | F<br>(mg/L)<br>2 a | Al<br>(μg/L)<br>1000 a | As<br>(μg/L)<br>10 <sup>a</sup> | B (mg/L) | Ba<br>(mg/L) |      | Cr (VI)<br>(µg/L) |         |       |       |      |      |     | Zn<br>(mg/L)<br>5a |
| Well 16 12/28/2004 475 290 8.3 206                            | 13           | 12           | 81     | 2.4  | 26              | 6.9  | _                       | 1.9                              | -                  | _                      | 7.1                             | 0.29     |              | 22   | 18.3              | < 0.05  | 0.043 | _     | <10  | _    | <25 | 0.055              |
|   | 7.5          | 4.4          | 98     | 1.9  | 38              | 9.3  | _                       | ND                               | _                  | ND                     | 13                              | 0.41     | 0.073        | 5    | -                 | ND      | ND    | _     | ND   | _    | ND  | ND                 |
| Well 16 4/13/2007 470 218                                     | 14           | 12           | 84     | 2.2  | 29.7            | 9    | 218                     | 0.5                              | _                  | _                      | 8.5                             | _        | -            | -    | _                 | _       | _     | _     | _    | -    | _   |                    |
| Well 16 6/18/2007   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 7.8                             | _        | -            | _    | -                 | -       | -     | -     | -    | -    | -   | _                  |
| Well 16 9/28/2007   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 7.8                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | _                  |
| Well 16 10/30/2007  | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 8.5                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | _                  |
| Well 16 11/28/2007  | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 8.7                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | _                  |
| Well 16 11/30/2007  | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 8.6                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | _                  |
| Well 16 12/4/2007   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 8.2                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | _                  |
| Well 16 1/24/2008   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 9.7                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | -                  |
| Well 16 1/30/2008   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 7.8                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | -                  |
| Well 16 1/31/2008 495 308 8.2 198                             | 14           | 12           | 82     | 2.3  | 30              | 7.9  | -                       | 1.9                              | -                  | ND                     | 7.8                             | 0.31     | 0.12         | 21   | -                 | 0.0037  | ND    | -     | ND   | -    | ND  | ND                 |
| Well 16 2/12/2008   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 9.7                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | -                  |
| Well 16 3/12/2008   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 9.9                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | -                  |
| Well 16 4/14/2008   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 8.1                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | -                  |
| Well 16 5/27/2008   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 7.9                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | -                  |
| Well 16 6/29/2008   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 7.8                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | -                  |
| Well 16 7/19/2008   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 7.5                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | -                  |
| Well 16 9/19/2008   | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 8.3                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | -                  |
| Well 16 11/13/2008  | -            | -            | -      | -    | -               | -    | -                       | -                                | -                  | -                      | 8.7                             | -        | -            | -    | -                 | -       | -     | -     | -    | -    | -   | -                  |
| MW-16-1430ft 11/19/2002 460 280 7.8 230                       | 18           | 19           | 63     | 2.7  | 19              | 6.5  | 230                     | 2.1                              | -                  | < 50                   | 7.4                             | 0.18     | 0.21         | 50   | -                 | < 0.05  | < 0.1 | -     | <10  | -    | <25 | < 0.05             |
| MW-16-1430ft 7/5/2007 470 302 - 234                           | 19           | 21           | 53.4   | 2.5  | 15.94           | 6.73 | 337                     | 0.63                             | -                  | <20                    | 2.3                             | -        | 0.2          | 50   | -                 | < 0.002 | -     | -     | -    | -    | <5  | < 0.02             |
| MW-16-1464-1604 9/20/2002 490 330 8.3 200                     | 8.7          | 6.6          | 110    | 2.1  | 42              | 11   | 200                     | <1                               | -                  | -                      | 11                              | _        | _            | -    | _                 | _       | _     | _     | _    | -    | _   | _                  |
| MW-98A 11/16/1998 500 271 7.67 -                              | 21           | 27.3         | 40.3   | 3.15 | 16.8            | 8.24 | 242                     | 2.24                             |                    | <50                    | <3                              | 0.111    | 0.214        | 24.2 | _                 | <0.005  | 1     | 0.461 | 35.1 | 37.6 | <4  | < 0.005            |
|   | 21.6         | 27.3         | 38.8   | 3.18 | 16.4            | 7.72 | 253                     | 2.24                             | -                  | -50                    | -                               | 0.111    | 0.214        | 24.2 |                   | < 0.005 |       | 0.197 | 34   | 33.8 | -   | < 0.005            |
|   | 13.6         | 6.01         | 84     | 5.22 | 25.6            | 7.88 | 259                     | <0.1                             |                    | <50                    | 4.7                             | 0.28     | 0.0672       | <5   |                   |         |       | 0.813 |      | 47   |     | 0.0345             |
|   |              |              |        |      |                 |      |                         |                                  | -                  |                        |                                 |          |              |      |                   |         |       |       |      |      |     |                    |
|   | 11.1         | 8.4          | 93.9   | 1.86 | 43              | 7.41 | 238                     | 0.32                             | -                  | <50                    | <2                              |          | 0.107        | <5   |                   |         |       | 0.774 |      | 34.5 |     | < 0.005            |
|   | 24           | 18           | 74     | 3.9  | 41              | 13   | 220                     | 3.6                              | -                  | <50                    | 3.3                             | 0.22     | < 0.1        | 17   | 12                | < 0.05  | < 0.1 | -     | 38   | -    | <5  | < 0.05             |
| SCWA-MainePrairie MW-2170   4/29/2008   600   380   7.9   260 | 10           | 5.3          | 130    | 1.6  | 35              | 16   | 260                     | <2                               | -                  | <50                    | 5.2                             | 0.31     | 0.12         | <10  | <1                | < 0.05  | < 0.1 | < 0.1 | 38   | 37   | <5  | < 0.05             |
| SCWA-Allendale MW-1925 3/26/2008 620 360 7.58 230             | 23           | 37           | 62     | 3.9  | 61              | 17   | 230                     | <2                               | -                  | <50                    | 3                               | 0.39     | 0.12         | 13   | 11                | < 0.05  | < 0.1 | < 0.1 | 63   | 63   | <5  | < 0.05             |
| SCWA-Dixon MW-2212 10/1/2009 530 310 8.25 200                 | 7.8          | 4.3          | 110    | 1.3  | 47              | 20   | 200                     | <2                               | -                  | <50                    | 3.5                             | 0.74     | < 0.1        | <10  | <1                | < 0.05  | < 0.1 | < 0.1 | 21   | 24   | <5  | < 0.05             |
| RNVWD MW-1389ft 9/9/1998 533 344 7.67 - 2                     | 29.2         | 18.7         | 54     | 4.51 | 34.2            | 8.99 | 248                     | 6.07                             | -                  | <50                    | 6.3                             | 0.125    | 0.0865       | <5   | -                 | < 0.005 | 1.06  | 0.43  | 41.2 | 39   | <4  | < 0.005            |

## Table 2-5 (continued) Groundwater Quality Northern Solano County

|             |      |                          |                        |                 |                                 |              | Cati         | ions         |             |   | Anions                               |   |     |                     |          |  | Trace             | Eleme  | nts |        |  |  |
|-------------|------|--------------------------|------------------------|-----------------|---------------------------------|--------------|--------------|--------------|-------------|---|--------------------------------------|---|-----|---------------------|----------|--|-------------------|--------|-----|--------|--|--|
| Well Name D | Date | EC<br>(μmho/cm)<br>900 b | TDS<br>(mg/L)<br>500 b | рН<br>6.5/8.5 b | Total 1<br>Alkalinity<br>(mg/L) | Ca<br>(mg/L) | Mg<br>(mg/L) | Na<br>(mg/L) | K<br>(mg/L) | SO <sub>4</sub><br>(mg/L)<br>250 <sup>b</sup> | HCO <sub>3</sub> <sup>1</sup> (mg/L) | - | 711 | As<br>(μg/L)<br>10a | B (mg/L) |  | Cr (VI)<br>(μg/L) | (mg/L) |     | (mg/L) |  |  |

- 1. HCO3, Total Alkalinity and NO3 reported as HCO3, CaCO3 and NO3 respectively.
- a) Primary Drinking Water Standards for California and Federal Maximum Contaminant Levels
- b) Secondary Drinking Water Standards for California and Federal Maximum Contaminant Levels
- c) California State Notification Level

<sup>&</sup>quot;-" Not Analyzed; ND = Non-Detect (Reporting Limit unknown)
For repeated sampling within a day, the maximum result for each constituent for the day is shown
Bold indicates value exceeds Water Quality Limit

Table 3-1
City of Vacaville Groundwater Monitoring Program<sup>1</sup>

|                         |                |                       | Perforated                 | Water I     | _evels     |                                 | Water C    | Quality <sup>3</sup> |         | Proc   | duction    |
|-------------------------|----------------|-----------------------|----------------------------|-------------|------------|---------------------------------|------------|----------------------|---------|--------|------------|
| Well Type               | Well ID        | Formation             | Interval <sup>2</sup> (ft) | Manual      | Electronic | General<br>Mineral/<br>Physical | Inorganics |                      | Nitrate | Manual | Electronic |
|                         | Well 1         | Markley               | Depth = 605                | Semi-annual | -          |                                 |            |                      |         | -      | SCADA      |
|                         | Well 2         | Basal & Middle Tehama | 335-710                    | -           | -          |                                 |            |                      |         | Daily  | -          |
|                         | Well 3         | Basal & Middle Tehama | 420-900                    | -           | -          |                                 |            |                      |         | Daily  | -          |
|                         | Well 5         | Basal Tehama          | 588-793                    |             |            |                                 |            |                      |         | -      |            |
|                         | Well 6         | Basal Tehama          | 752-932                    |             |            |                                 |            |                      |         | -      |            |
|                         | Well 7         | Basal Tehama          | 964-1004                   |             |            |                                 |            |                      |         | -      |            |
| Production              | Well 8         | Basal Tehama          | 952-1192                   |             |            | Triennial                       | Triennial  | Triennial            | Annual  | -      |            |
|                         | Well 9         | Basal Tehama          | 1100-1430                  | Semi-annual | SCADA      |                                 |            |                      |         | -      | SCADA      |
|                         | Well 13        | Basal & Middle        | 560-840                    | Semi-amuai  |            |                                 |            |                      |         | -      |            |
|                         | Well 14        | Basal Tehama          | 1108-1663                  |             |            |                                 |            |                      |         | -      |            |
|                         | Well 15        | Basal Tehama          | 1206-1816                  |             |            |                                 |            |                      |         | -      |            |
|                         | Well 16        | Basal Tehama          | 1165-1610                  |             |            |                                 |            |                      |         | -      |            |
|                         | DeMello        | Upper Tehama          | 372-572                    |             | -          |                                 |            |                      |         | Daily  | -          |
|                         | MW-14          | Basal Tehama          | 1100-1650                  |             | Transducer |                                 |            |                      |         |        |            |
|                         | MW-15-188'     | Qal & Upper Tehama    | 158-178                    |             | -          |                                 |            |                      |         |        |            |
|                         | MW-15-508'     | Upper Tehama          | 438-498                    |             | -          |                                 |            |                      |         |        |            |
|                         | MW-15-1815'    | Basal Tehama          | 1207-1785                  |             | Transducer |                                 |            |                      |         |        |            |
|                         | MW-16-117'     | Upper Tehama          | 97-107                     |             | -          |                                 |            |                      |         |        |            |
| Monitoring <sup>4</sup> | MW-16-1176'    | Basal Tehama          | 1136-1166                  | Semi-annual | -          | NA                              | NA         | NA                   | NA      | NA     | NA         |
|                         | MW-16-1430'    | Basal Tehama          | 1264-1374                  |             | Transducer |                                 |            |                      |         |        |            |
|                         | MW-98A         | Basal Tehama          | 1727-1830                  |             | Transducer |                                 |            |                      |         |        |            |
|                         | MW-98B         | Basal Tehama          | 1559-1798                  |             | -          |                                 |            |                      |         |        |            |
|                         | MW-98C         | Basal Tehama          | 2152-2305                  |             | Transducer |                                 |            |                      |         |        |            |
|                         | DeMello-MW-95' | Qal                   | 65-85                      |             | -          |                                 |            |                      |         |        |            |

- 1. Does not include shallow monitoring wells at wastewater treatment plants.
- 2. Depth to top and bottom of perforated interval, if available. Otherwise, total well depth shown.
- 3. Does not include weekly monitoring of the distribution system for coliform bacteria, chloride residual, etc..
- 4. Transducers to be installed in monitoring wells before January 1, 2011.

NA - Not applicable

Table 3-2
Summary of SCWA Monitoring Well Construction

| Well ID <sup>1</sup>   | Depth<br>(ft)                                     | Perforated<br>Interval<br>(ft)  | Diameter<br>(in)                             | Began<br>Monitoring<br>Water Levels  |
|--|---|---|--|--|
| Allendale 1235 Allendale 1345 Allendale 1925 Dixon 1200 Dixon 2212   | 1235<br>1345<br>1925<br>1200<br>2212              | 1205-1225<br>1315-1335<br>1877-1917<br>1180-1190<br>2182-2202                     | 2.5<br>2.5<br>4/2 <sup>2</sup><br>2.5<br>4/2 | 8/7/2008<br>8/7/2008<br>8/7/2008<br>11/13/2009<br>11/13/2009                     |
| Dixon 2370  Maine Prairie 840  Maine Prairie 1960  Maine Prairie 2170  Meridian 400  Meridian 825  Meridian 1680 | 2370<br>841<br>1960<br>2170<br>400<br>824<br>1680 | 2340-2360<br>811-831<br>1930-1950<br>2140-2160<br>360-370<br>794-814<br>1650-1670 | 4/2 2.5 4/2 4/2 2.5 2.5 4/2                  | 8/7/2008<br>8/7/2008<br>8/7/2008<br>8/7/2008<br>8/7/2008<br>8/7/2008<br>8/7/2008 |

<sup>1.</sup> See Appendix X for as-built construction drawings and additional construction details.

<sup>2.</sup> Four-inch diameter with reduction to two-inch diameter.

#### Table 3-3 Summary of Action Items

| Plan Components and Action Items  |   | Long-term <sup>2</sup> | Continuing <sup>3</sup> |
|---|---|------------------------|-------------------------|
| CATEGORY 1: MONITORING PROGRAM  |   |                        |                         |
| 1A. Elements of Monitoring Program  |   |                        |                         |
| Continue City's existing monitoring program and complement with information gathered by other agencies  |   |                        | X                       |
| Expand regional monitoring programs   |   |                        |                         |
| <ul> <li>Coordinate with SCWA regarding adequacy of regional groundwater monitoring networks and programs</li> </ul>  | X |                        |                         |
| <ul> <li>Coordinate with SCWA on planned construction of additional monitoring facilities in northern Solano County</li> </ul>  | X |                        |                         |
| <ul> <li>Coordinate with SCWA on implementation of land subsidence monitoring program</li> </ul>  | X |                        |                         |
| 1B. Evaluation and Reporting of Monitoring  |   |                        |                         |
| <ul> <li>Prepare brief annual summary of groundwater and land subsidence data collected through March 31<sup>st</sup> in groundwater<br/>management report to be completed each year by June 30<sup>th</sup></li> </ul>       | X |                        |                         |
| <ul> <li>Coordinate with SWA-4 on maintenance and utilization of regional monitoring database, including regular transfer of<br/>City data. Also coordinate with SWA on monitoring protocols used to evaluate data</li> </ul> | X |                        |                         |
| Coordinate with SWA-4 regarding adequacy of regional evaluation and reporting of groundwater data (see Sect. 3.3.2)   | X |                        |                         |
| CATEGORY 2: WATER RESOURCE SUSTAINABILITY   |   |                        |                         |
| 2A. Maintaining Stable Groundwater Levels   |   |                        |                         |
| • Continue to manage groundwater and surface water conjunctively to ensure that groundwater levels in Elmira Road wells recover to spring 1992-1993 "base year" levels during normal years                                    |   |                        | X                       |
| Manage pumping away from Elmira Road to prevent progressive groundwater level declines  |   | X                      |                         |
| • Continue groundwater development programs that optimize pumping distribution in City's urban planning area  |   |                        | X                       |
| 2B. Determination of Sustainable Pumpage  |   |                        |                         |
| Assess pumpage relative to sustainable yield of principal aquifer system  |   |                        |                         |
| Update sustainable pumpage estimates with expanded monitoring data  |   | X                      |                         |
| Refine assessment of hydrogeologic conditions and conceptual model in preparation for future development of   |   | X                      |                         |
| regional numerical groundwater flow model (see Section 3.4.2)   |   | 11                     |                         |
| <ul> <li>Discuss joint development of regional numerical groundwater flow model with SCWA and other entitles that overlie<br/>subbasin</li> </ul>   |   | X                      |                         |


# Table 3-3 (continued) Summary of Action Items


| Plan Components and Action Items  |   | Long-term | Continuing |
|---|---|-----------|------------|
| 2C. Continuation of Conjunctive Use Operations  |   |           |            |
| Continue City's conjunctive management of available water resources   |   |           | X          |
| Coordinate with SCWA to explore other conjunctive use opportunities   |   |           |            |
| 2D. Water Conservation  |   |           |            |
| Continue to implement and promote water conservation programs   |   |           | X          |
|   |   |           |            |
| CATEGORY 3: GROUNDWATER RESOURCE PROTECTION   |   |           |            |
| 3A. Well Construction and Destruction Policies  |   |           |            |
| Continue current well construction and destruction policies   |   |           | X          |
| <ul> <li>Coordinate with other SCWA members on well construction and future resource utilization</li> </ul>   |   | X         |            |
| 3B. Identification and Management of Recharge Areas and Wellhead Protection Areas   |   |           |            |
| <ul> <li>Employ wellhead protection measures to ensure long-term sustainability of good quality water</li> </ul>  |   |           |            |
| <ul> <li>Use DWSAP information, including delineation of source area and protection zones</li> </ul>  | X |           |            |
| <ul> <li>Require deep sanitary seal construction standards for municipal supply wells</li> </ul>  |   |           | X          |
| <ul> <li>Employ well destruction policy to prevent groundwater contamination</li> </ul>   |   |           | X          |
| <ul> <li>Coordinate with other SCWA members regarding DWSAP analyses and other environmental assessments</li> </ul>   |   | X         |            |
| • Promote recharge area protection to mitigate impacts of urban infrastructure and sources of groundwater contamination   |   | X         |            |
| 3C. Management and Mitigation of Contaminated Groundwater   |   |           |            |
| <ul> <li>Identify short and longer-term water quality trends and actions needed to sustain supply of good quality groundwater</li> </ul>  |   | X         |            |
| Employ BMPs to limit potential sources of contamination   | X |           |            |
| <ul> <li>Coordinate with County Environmental Health Services Division and other land use/regulatory agencies to identify and mitigate any public water supply contamination</li> </ul> | X |           |            |
| Coordinate with SCWA members and County Environmental Health Services Division to assess quality of groundwater used by private well owners in subbasin                                 |   | X         |            |
| 3D. Long-Term Salinity Management Programs  |   |           |            |
| Implement measures to avoid salt accumulation and other adverse changes in groundwater chemistry  |   | X         |            |

# **Table 3-3 (continued) Summary of Action Items**


| Plan Components and Action Items   |          |   | Continuing |
|--|----------|---|------------|
| CATEGORY 4: AGENCY COORDINATION AND PUBLIC OUTREACH  |          |   |            |
| 4A. Continuation of Local, State, and Federal Agency Relationships   | <u> </u> |   |            |
| <ul> <li>Continue relationships with local, state, and federal agencies to achieve broader local and regional benefits</li> </ul>  |          |   | X          |
| <ul> <li>Continue to pursue grant opportunities with SCWA to fund basin management activities and regional water projects</li> </ul>   |          |   | X          |
| 4B. Public Outreach  |          |   | 1          |
| Continue public involvement through City Council meetings that include updates on water resource management  |          |   | X          |
| Continue public outreach on Plan activities through web site, bill inserts, radio spots, and printed media   |          |   | X          |
| 4C. Water Awareness Education  |          |   |            |
| Continue water awareness education programs  | 1        |   | X          |
| CATEGORY 5: PLAN IMPLEMENTATION AND UPDATES  |          |   | ı          |
| 5A. Plan Implementation and Reports  |          |   | I          |
| Cooperate with other agencies  |          |   | 1          |
| o Provide copies of adopted Plan, and related reports, to SCWA/SWA members   | X        |   |            |
| <ul> <li>Continue to support IRWMP, including implementation of priority objectives</li> </ul>   |          |   | X          |
| Prepare groundwater management reports   |          |   |            |
| <ul> <li>Prepare annual groundwater management reports to be completed by August 1<sup>st</sup>. Reports will summarize activities conducted to implement Plan and include summary of monitoring data collected through March 31<sup>st</sup></li> </ul> | X        |   |            |
| o Coordinate with SWA to prepare update of groundwater conditions in subbasin every five years   |          | X |            |
| 5B. Provisions to Update the Groundwater Management Plan   |          |   |            |
| Review and update plan every five years or more often as needed  |          | X |            |


- 1. Short-term actions are items to be completed within two years.
- 2. Long-term actions are items expected to require more than two years.
- 3. Continuing are items that are ongoing groundwater management activities.






File: Y:\Casey\_Meirovitz\10-1-124 Vacaville GWMP Update\Report\GIS\Figure 1-1 City of Vacaville Location Map.mxd Date: 12/15/2010












Figure 2-4 City of Vacaville Annual Groundwater Pumpage








Figure 2-5 Surficial Geologic Map of Solano County

















Figure 2-8 Groundwater Level Hydrograph City of Vacaville, Well No. 8











File: Y:\Casey\_Meirovitz\10-1-124 Vacaville GWMP Update\Report\GIS\Figure A-3 WL Hydrograph for all zones.mxd Date: 12/15/2010





Figure A-4
Representative Hydrographs of Basal Zone Wells


## **Well 15**



File: Y:\Casey\_Meirovitz\10-1-124 Vacaville GWMP Update\Report\Figures|Figure A-5 Well 15 Hydrograph Date: 12/9/2010



## **Well 16**



ille: Y:\Casey Meirovitz\10-1-124 Vacaville GWMP Update\Report\Figures|Figure A-6 Well 16 Hydrograph Date: 12/9/2010



Figure A-6 Hydrographs, City Well No. 16 and Nearby Monitoring Wells

